KRISHANAN LAND

9.45 (31'0")

AURMUGAM LAND

36.58 (120'0")

DURAISAMY LAND

36.58 (120'0")

SHOP
6.54 x 20.54

R.C.

7.88

1.50

N

SOLAR SYSTEM

SOLAR SYSTEM

ELEVATION

3.66

20.54 M

Colour Sheet Roof
Steel Truss
Brick Work In C.M.1:5
Lintel Beam C.C.1:2:4
Floor Finish
Floor Finish In1:4:8
Earth And Sand Filling
R.C.C. Plinth Beam
R.C.C. Column 1:2:4:
R.C.C. Footing
P.C.C.1:2:4

SECTION ON ' AB '

To Bargur --->

9.14 (30'0")

--- North - South Anthiyur - Bargur Main Road ---

12.18 M

<--- To Anthiyur

GROUND FLOOR WITH SITE PLAN

Nalam Hospetal

— Road —

A L P M Mahal
Anthiyur

Indian Oil
Petrol
Bunk

Bharath
Petroleum

North - South Anthiyur - Bargur Main Road

— East - West Road —

LOCATION OF THE SITE

TOPO PLAN
NOT TO SCALE

1'1.5" 3.05 M (10'0") 1'1.5"

7.5 C.M. Ht. Dwarf Wall

R.C.C. Pillags 1'1.5" x 1'1.5"

COMPOUND WALL PLAN

COMPOUND ELEVATION

BRICK WALL
PLINTH BEAM
P.C.C. 1:4:8
SAND FILLING

SECTION ON " B C "

VENT PIPE
"U" TRAP
R.C.C. COVERING SLAB 0.10 M THICK
MANHOLE
BRICK WORK IN C.M 1:5
PLASTERED IN C.M 1:3
P.C.C. 1:5:10

SEPTICK TANK & DISPERSION TRINCH

LONGITUDINAL SECTION IN " XX "

PLAN

16 MM Dia 4 No. Main Rod's
Plinth Beam Size 0.45 x 0.23
4 No's 16 MM Dia Rod's
Footing Concrete R.C.C.
M20 0.45 x 045 x 0.23
12 MM Dia @ 0.15 C/C
Bothways.
P.C.C. 1:4:8 Mix
Sand Filling

FOUNDATION DETAIL

O.H.T
INLET
STAINLESS STEEL TANK
STAND
OUTLET
O.T.S. LEVEL
SOLAR COLLECTOR

BUILDING
RAINWATER PIPE
CONCRETE SLAB
SAND
BRICK BATS
TOILET
FILTER BED
2'0" x 2'0" x 3'0"
BORE WELL

PLAN

RAINWATER HARVESTING TANK
NOT TO SCALE

SOLAR WATER HEATING SYSTEM

G.L
LOOSE SOIL
ORDINARY GRAVEL
HARD GRAVEL
HARD STRUT

TRIAL PIT DETAILS

Signature Not Verified
Signed by: Executive Officer
Location: Erode
Date: 2024.01.22 19:46:00

Office Use:

Building Plan Approval No : 73/2023-2024
Date : 22.01.2024

Licence Period : 22.01.2024 to 21.01.2029

PLAN SHOWING THE PROPOSED CONSTRUCTION OF COLOUR SHEET ROOF FLOOR SHOP BUILDING IN Re - S.F.No. 972/6 AT ANTHIYUR To BARGUR MAIN ROAD, ANTHIYUR TOWN PANCHAYAT & VILLAGE, ANTHIYUR TALUK, ERODE DISTRICT.

AREA DETAILS	Sq. METER	Sq. FEET
AREA OF THE SITE	340.15	3,660.00
PRO.COLOUR SHEET ROOF	147.00	1582.00
TOTAL FLOOR AREA	125.25	1,348.00
OPEN SPACE AVAILABLE	193.15	2,078.00

REFERENCE	METER	FEET
R.S. - Rolling Shutter	6.00 x 2.13	20'0" x 7'0"
D - Door	1.22 x 2.13	8'0" x 7'0"
W - Window	2.44 x 1.22	8'0" x 4'0"
V - Ventilator	2.44 x 0.61	8'0" x 2'0"

Colour Index:
Site Boundary
Proposed Construction

Note:
Solar Water Heater To Provided 1No Collection Tank
Water Will Be Reuse Toilet And Bath Purpose.

Consultant & Drawing By, Cell: 94432-54764.
Er.S.VIJAYASUNDARAM.
D.C.E., B.TECH., (CIVIL) , L.B.S.
SRI BALAVINAYAGAR CONSTRUCTION
Email - vijayc.edd.gobi@gmail.com,
Sathy, Gobi, Anthiyur

ENGINEER & L.B.S.

Er.S.VIJAYASUNDARAM
D.C.E., B.Tech., L.B.S.,
Licenced Building Surveyor
(Anthiyur Town Panchayat)
Cell : 9443254764, 9500678969

Engineer.

Applicant
Thiru. A.SHANMUGAM, S/o. ALAGIYA GOUNDER.