PP APPROVAL RECORD

Planning Permission

Erode

Erode district, Tamil Nadu

APPROVAL TYPE
Building Plan

ISSUING AUTHORITY
DTCP

The approval as the planning authority issued it, reproduced in full behind this page.

An approval speaks to what was sanctioned, not to what was built. Completion is a separate record.


Verified RealEstate™

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India


hello@verified.realestate

+91 9996 12 9996


verified.realestate




ELEVATION



SECTION ON " AB "




SECTION ON " CD "



SEMI-BASEMENT FLOOR PLAN SCALE 1:200

MODEL	QTY.	CAR SPACES	USABLE PLATFORM DIMENSION		MAX.ALLOW. VEHICLE LOAD	MAX. SUITABLE DIMENSION FOR VEHICLE			
			WIDTH	LENGTH		LOWER HT.	*UPPER HT.	WIDTH	LENGTH
STACKER SR 220	9	18	2200	4000	2000 kg	2000	1500	1800	5000
STACKER SR 210	3	6	2100	4000		2000	1500	1700	5000
TOTAL STACKERS AND CAR SPACES	12	24							




ELECTRICAL REQUIREMENT (PURCHASER'S SCOPE)

1) INCOMING SUPPLY :
3Ph 415VAC (± 10%), 50Hz (± 2%), WITH NEUTRAL & EARTH (5PH+N+E) PER UNIT.
2) CONTROL SWITCHGEAR :-
4 POLE RCBO (OR ELCB+MCB) 25 AMP (C-CURVE) WITH ENCLOSURE.
3) INCOMING CABLE SIZE :-
5 CORE X 6.0 SQ. mm FLEXIBLE COPPER MULTI CORE CABLE (3PH+N+E)
FROM MAIN SWITCH TO CONTROL PANEL UNIT. (PER UNIT).

ELECTRICAL CONNECTION TO BE PROVIDED (PURCHASER'S SCOPE)

POWER PACK SIZE - L630mm x W550mm x H 1primeval)
FOR EACH HYDRAULIC POWER PACK (3.7 KW)

STACKER - LOAD PLAN



SYSTEM IS BOLTED TO THE FLOOR - DRILLING DEPTH APPROX. 60mm.
SYSTEM IS SUPPORTED TO THE WALL & CEILING - DRILLING DEPTH APPROX. 40mm.
FLOOR AND WALLS ARE TO BE MADE OF CONCRETE
(GRADE OF CONCRETE M15/M20)

STACKER - LOAD PLAN

LOAD PLAN (For all variants)	FORCES IN kN				
PLATFORM LOAD	F1	F2	F3	F4	±1
2,000 kg	30	1.1	7.4		±1

IMPORTANT NOTES AND CUSTOMER SCOPE OF WORK :


1) This Car parking layout is prepared based on the customers Layout, if there exists any deviations in the layout after construction, we Park layer have right to modify the dimensions of the equipment accordingly.
2) As per the Specifications and Locations shown in this layout, the installations of the Parking system will be carried out.
3) Since Multiple parking stacks are connected to a single Powerpack, only one stacker can be operated at one time in a group, which are connected their Powerpack.
4) The Painting colour on the structurals of the stacker is Park layer standard Green with Grey finish. If customer requires any customised colour, then additional cost may apply.
** 5) The Clear height from the Floor to the Ceiling is considered as shown in the Section. In case there is a variation in this Dimension, the Car height which can be accommodated on either parking space will vary accordingly
6) The customer to provide Min flooring thickness & Grade required for anchoring of the parking system.
7) Over the Stacker installation areas all Electrical devices, Cable tray, Water Sprinkler must be installed above the Clear height mentioned in the section. Otherwise car space height will get reduced.
8) Electrical points as per the specifications shown must be provided by the customer in the installation points as shown in the Layout.
9) The provisions must be made to arrest the water seepage in the parking area.
10) Proper Shade or Canopy to be provide above the Car parking systems at open areas (Customer's scope)
11) Sufficient Lighting arrangement to be provided in the parking area.

PARKABILITY :-


1) If the Available distance between the columns is less to accommodate the standard stackers the platform width that can be provided shall be less. Parking on such a smaller platform may be difficult. This depends on Type of Vehicle, its approach into the platform and Individual driver's skill.
2) If the Driveway width less than Normal as shown in some areas there may be difficulty in turning the Vehicle. Two or more Laps may be required to park and retrieve the Cars.

The Parkability of the Car also depends on :


a) Drive way width b) Better platform width to car width ratio c) Turning Radius of Car
d) Individual driver's skill e) Location of Car space (Corner car spaces will be difficult to drive into)
f) Door opening space will depend on: Platform width , Parking alignment on Platform, Distance between adjacent car spaces / Wall.




STAIRCASE DETAILS
Not to scale



SOLAR SYSTEM




SITE PLAN / SEMI-BASEMENT FLOOR PLAN





GROUND FLOOR PLAN

FIRST FLOOR PLAN



SOLAR PANEL FLOOR PLAN





VERTICAL REINFORCEMENT AT JAMPS OF OPENINGS

SURVEYOR / ASSISTANT DRAUGHTSMAN	J.Srinivasan
DRAUGHTSMAN - III GRADE	K.Velmurugan
SUPERVISOR / DRAUGHTSMAN - II GRADE	G.Kannan

PLAN SHOWING THE PROPOSED CONSTRUCTION OF R.C.C. TERRACED ROOF SEMI-BASEMENT, GROUND & GALVALUME SHEET ROOF FIRST FLOOR BUILDING FOR " COMMERCIAL / OFFICE PURPOSE " IN R.S.F. NO. 97/2A1, 97/2B1A, SURAMPATTI VILLAGE, AT PERUNDURAI ROAD, SURAMPATTI, ERODE CITY MUNICIPAL CORPORATION, ERODE TALUK & DISTRICT.

APPLICANTS:-

1. Mr. K.P.SHIVASHANKAR & 4 MEMBERS

SWP/BPA/0235219/2024

SWP / DTCP / ERODE(LPA) / SITE APPROVAL NO. 221 / 2024

SWP / DTCP / ERODE(LPA) / PLANNING PERMISSION NO. 22 / 2024

AREA DETAILS		SQ.M
AREA OF THE APPLICANT SITE	[as per Document]	758.00
	[as per Survey Record]	758.00
	[Super Imposed Plot]	758.00

AREA DETAILS	Total Buildup [SQ.M]	Non FSI Area	Commercial FSI Area [SQ.M]
AREA OF THE SEMI-BASEMENT	482.89	482.89	--
AREA OF THE GROUND FLOOR	482.89	--	482.89
AREA OF THE FIRST FLOOR	482.89	--	482.89
TOTAL	**1448.67**	**482.79**	**965.78**

JOINERY DETAILS		METRE
RS	ROLLING SHUTTER	6.00 X 2.44
RS1	ROLLING SHUTTER	4.00 X 2.44
D	DOOR	1.00 X 2.13
D1	DOOR	0.76 X 2.13
W	WINDOW	1.83 X 1.83
V	VENTILATOR	1.00 X 0.76

PARKING DETAILS	Required	Provided
CAR PARKING	10+1	12
TWO WHEELER	39+4	44

PLOT COVERAGE
$\frac{482.89}{758.00}$ X 100 = 63.71%

FLOOR SPACE INDEX
$\frac{965.78}{758.00}$ = 1.27

COLOUR INDEX
- SITE BOUNDARY
- PROPOSED BUILDING
- EXISTING ROAD

SCALE 1:100

ALL DIMENSIONS ARE IN "METRE"

STRUCTURAL

M.P. SURESHKUMAR M.E
REGD.STRUCTURAL ENGR. GRADE-I
710/2020/RSE-GR.I/EDTCP
18-A,CHENNIMALAI ROAD,
OPP. TO ITI,ERODE-638009.

APPLICANT	ENGINEER/LBS
K.P. Shivashankar M.P. Sureshkumar S. Madhumathi	Er.S.V.GURUNATHAN B.E.,M.I.E. PGDIGEVI., Civil Engineer & RE Reg.No:01 2019 RE-GR- II - ELPA GURU PLANNERS & DESIGNERS 101, K.P.G. Complex, Carmel School (Opp.) Anur Bye-Pass Road, Kallampalayam, ERODE-638 002. Ph : 97154 66665.

THE LANDLENS SUITE

Eight ways to know a piece of land before you pay for it.

This report covers one part of the picture. These cover the rest, drawn from the same government records, for any property in Tamil Nadu.

LandLens One
Ask anything about a property and get an answer grounded in live government records, with the sources shown.
/landlens/one

Verify My Land
Every record check run on one property and returned as a single report.
/landlens/verify-my-land

Legal Opinion
An advocate's written opinion on the title, built on the records we pull for it.
/landlens

One Map
Every layer on one map: the parcel, its boundary, zoning, water bodies and what sits around it.
/landlens/one/map

PriceMap
What land actually changed hands for around this plot, taken from the registered deeds.
/landlens/pricemap

Build Scope
What you are allowed to build here: floor space, height, coverage and setbacks.
/landlens/build-scope

Property Tracker
Watch a property and hear about it when something new is registered against it.
/landlens/property-tracker

Deal Room
Run the transaction in one place: documents, stamping, signatures and the parties.
/landlens/deal-room

FREE TOOLS · NO ACCOUNT NEEDED

Twenty-four checks you can run yourself, at no cost.

Records and verification

The registers themselves, read for you.

- Encumbrance Certificate
- Patta and Chitta
- Field Measurement Sketch
- EC Analyzer
- Bank charge check
- Court case search
- Seller background check
- Approval check by survey

Value and duty

What it is worth and what it costs to register.

- Guideline value by street
- Guideline value by survey
- Stamp duty and registration fees
- Capital gains
- Floor space index
- Area unit converter

Zoning and land use

What the plan says can happen on this land.

- Land use zone finder
- CMDA land use check
- Coastal regulation zone
- Master plan check
- Water bodies finder
- Airport height clearance

Registers and directories

Who holds it, and which office keeps the record.

- Find your registering office
- Temple property check
- Waqf property check
- RERA register

Every free tool
/tools

Services we run for you
/services

The LandLens suite
/landlens/one

Verified RealEstate™

Every claim in this document traces back to a government record.

- Legal opinions, due diligence and title verification
- Building plan, layout and sub-division approvals
- Completion and occupancy certificates, regularisation
- Escrow, negotiation and NRI property management
- Land survey, soil testing, architecture and construction

Verified RealEstate
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India
hello@verified.realestate
+91 9996 12 9996

Prepared from the registers named on the page each finding sits on. Where a register could not be read, this document says so in its place rather than leaving the gap to be read as a clean result.