PP APPROVAL RECORD

Planning Permission

Madurai district, Tamil Nadu

APPROVAL TYPE
Building Plan


ISSUING AUTHORITY
DTCP

The approval as the planning authority issued it, reproduced in full behind this page.


An approval speaks to what was sanctioned, not to what was built. Completion is a separate record.

Verified RealEstate™
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India


hello@verified.realestate
+91 9996 12 9996
verified.realestate




SECTION BB



NORTH FACING ELEVATION




SECTION AA



TERRACE FLOOR PLAN


FIRST, SECOND FLOOR PLAN
(TYPICAL)




STILT CUM GROUND FLOOR PLAN


SITE PLAN


1.0மீ அகல மாற்றி அமைக்கப்பட வேண்டிய நிலவியல் நீர்வழிப்பாதை





NOT TO SCALE











SHEET NO :1/1

DETAILED PLAN SHOWING THE PROPOSED CONSTRUCTION OF COMMERCIAL BUILDING (PROFESSIONAL CONSULTING OFFICE) AT R.S.NO: 166/9A1B ANNUPANADI VILLAGE, MADURAI SOUTH TALUK,MADURAI CORPORATION, MADURAI DISTRICT.

SCALE 1:100 | ALL DIMENSIONS ARE IN METER

SITE AREA

AS PER DOCUMENT = 910.54 Sq.m
(Least Area to be considered)
AS PER PATTA = 911.00 Sq.m
AS IN SITE/FMB = 913.08 Sq.m

AREA STATEMENT

FLOOR DETAILS	F.S.I AREA (SQ.M)	NON F.S.I AREA (SQ.M)	DEDUCTION AREA (SQ.M)	FLOOR AREA (SQ.M)
STILT CUM GROUND FLOOR	291.25	142.47	-	433.72
FIRST FLOOR	433.72	-	-	433.72
SECOND FLOOR	433.72	-	-	433.72
TERRACE FLOOR STAIR CASE	-	21.30	-	21.30
TOTAL BUILT UP AREA	**1158.69**	**163.77**	-	**1322.46**

FSI CALCULATION:

ALLOWABLE FSI = 2.0

FSI = TOTAL COVERD AREA / SITE AREA = 1158.69 / 910.54 = 1.27 < (2.0)

JOINERY DETAILS

RS	ROLLING SHUTTER	1.20 x 2.13
MD	DOOR	1.70 x 2.13
D	DOOR	1.20 x 2.13
D1	DOOR	0.65 x 2.13
W	WINDOW	1.50 x 1.50
W1	WINDOW	2.00 x 1.50
W2	WINDOW	3.00 x 1.50
V	VENTILATOR	1.00 x 0.76

PARKING DETAILS:-

Commercial For (OFFICE) = 1158.69 Sq.m
1 Car Space for every 100 Sq.m of floor area and 1 Two wheeler Space for every 25 Sq.m of floor area

Car = 1158.69 / 100 = 12 Nos

two wheeler = 1158.69 / 25 = 47 Nos

*Shall be provided for 75% of total Parking Spaces Required
Required Car Parking =12 x 75% = 09Nos
Required Two Wheeler Parking = 47 x 75% = 35Nos

*Visitor provided for 10% of total Parking Spaces Required
Required Car Parking =09 x 10% = 1 Nos
Required Two Wheeler Parking =35 x 10% = 4Nos

PARKING DETAILS:-	REQUIRED	PROVIDED
TWO WHEELER PARKING	39	40
CAR PARKING	10	10

SANITARY CALCULATION

SANITARY DETAILS:-	TOTAL NUMBER OF PERSONS -25 NOS		
	MALE-25	FEMALE-25	
SANITARY UNIT	SANITATION REQUIREMENT FOR COMMERCIAL BUILDING	REQUIRED NOS	PROVIDED NOS
DA WATER CLOSET	PH WATER CLOSET MINIMUM ONE PROVIDED	1	1
MALE WATER CLOSET	MALE WATER CLOSET ONE FOR EVERY 25 PERSONS	1	1
FEMALE WATER CLOSET	FEMALE WATER CLOSET ONE FOR EVERY 15 PERSONS	2	2
DRINKING WATER FOUNTAIN	DRINKING WATER FOUNTAIN ONE FOR EVERY 100 PERSONS	1	2
WASH BASIN	WASH BASIN ONE FOR EVERY 25 PERSONS	2	2
URINALS	URINALS ONE FOR 21-45 PERSONS	2	2
CLEANER SINK	ONE PER FLOOR MINIMUM,PREFERABLY IN OR ADJACENT TO SANITARY ROOMS	3	3

NOTE:

1. FIRE EXTINGUISHER TO BE PROVIDED. FE
2. FIRE ALARM TO BE PROVIDED. FA
3. RAIN WATER HARVESTING SYSTEM TO BE PROVIDED
4. SOLAR SYSTEM TO BE PROVIDED.
5. STRUCTURE IS DESIGNED SAFELY FOR EARTH QUAKE RESISTANCE
6. WASTE WATER TO BE CONNECTED TO UNDER GROUND SEWAGE SYSTEM
7. MECHANICAL VENTILATION TO BE PROVIDED.

திட்ட அனுமதி

மனை ஒப்புதல் மற்றும் திட்ட அனுமதி மதுரை உள்ளூர் திட்டகுழுமம், மதுரை -17 ந.க.எண்: SWP/BPA/0783214/2026/TCP உத்தரவில் கண்டுள்ளவாறு நிபந்தனைகளுக்குபட்டு 'A' முதல் 'G' வரை எல்லையிடபட்டு மனையிட ஒப்புதலும், கட்டிடத்திற்கு திட்ட அனுமதியும் அளிக்கப்படுகிறது.

ம.வ /ம.உ..திகு எண்:194/2026

திட்ட/அனுமதி எண்: 208/2026

LEGEND:

- SITE BOUNDARY
- BUILDING BOUNDARY
- EXISTING ROAD
- PROPOSED DRIVEWAY
- EV PARKING
- CHANNEL

APPLICANT	ENGINEER	ARCHITECT	STRUCTURAL ENGINEER
	Er. V.SUREYA PRAKASH B.E., REGISTERED ENGINEER GRADE-I 018/2024/RE-GR-I/DTCP/MADURAI 21B, First Floor, Kannadhasan Street, S.S.Colony, Madurai-16. Ph: 7373969777	R. Vinodh, B.Arch., COA REG. No: CA/2009/45825 ORANGE ARCHITECTS 25-D, Besant Road, Chinna Chokkikulam, Madurai-625 002. Ph: 0452-4217375	T. VEERAMANI B.E. STRUCTURAL ENGINEER 24J/1, Old Kuyavarpalayam Road 2nd Floor, Ralin Castle MADURAI - 652009 Reg. No. SE.02/2022 (Gr.II) Ph: 4512480

THE LANDLENS SUITE

Eight ways to know a piece of land before you pay for it.

This report covers one part of the picture. These cover the rest, drawn from the same government records, for any property in Tamil Nadu.

LandLens One
Ask anything about a property and get an answer grounded in live government records, with the sources shown.
/landlens/one

Verify My Land
Every record check run on one property and returned as a single report.
/landlens/verify-my-land

Legal Opinion
An advocate's written opinion on the title, built on the records we pull for it.
/landlens

One Map
Every layer on one map: the parcel, its boundary, zoning, water bodies and what sits around it.
/landlens/one/map

PriceMap
What land actually changed hands for around this plot, taken from the registered deeds.
/landlens/pricemap

Build Scope
What you are allowed to build here: floor space, height, coverage and setbacks.
/landlens/build-scope

Property Tracker
Watch a property and hear about it when something new is registered against it.
/landlens/property-tracker

Deal Room
Run the transaction in one place: documents, stamping, signatures and the parties.
/landlens/deal-room

FREE TOOLS · NO ACCOUNT NEEDED

Twenty-four checks you can run yourself, at no cost.

Records and verification

The registers themselves, read for you.

- Encumbrance Certificate
- Patta and Chitta
- Field Measurement Sketch
- EC Analyzer
- Bank charge check
- Court case search
- Seller background check
- Approval check by survey

Value and duty

What it is worth and what it costs to register.

- Guideline value by street
- Guideline value by survey
- Stamp duty and registration fees
- Capital gains
- Floor space index
- Area unit converter

Zoning and land use

What the plan says can happen on this land.

- Land use zone finder
- CMDA land use check
- Coastal regulation zone
- Master plan check
- Water bodies finder
- Airport height clearance

Registers and directories

Who holds it, and which office keeps the record.

- Find your registering office
- Temple property check
- Waqf property check
- RERA register

Every free tool
/tools

Services we run for you
/services

The LandLens suite
/landlens/one

Verified RealEstate™

Every claim in this document traces back to a government record.

- Legal opinions, due diligence and title verification
- Building plan, layout and sub-division approvals
- Completion and occupancy certificates, regularisation
- Escrow, negotiation and NRI property management
- Land survey, soil testing, architecture and construction

Verified RealEstate
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India
hello@verified.realestate
+91 9996 12 9996

Prepared from the registers named on the page each finding sits on. Where a register could not be read, this document says so in its place rather than leaving the gap to be read as a clean result.