



PLAN SHOWING THE ADDITIONAL PROPOSED CONSTRUCTION OF A.C SHEET ROOF "2030 - POULTRY FEED AND CATTLE FEED" (ORANGE CATEGORIES) "M/s. MAHENDRA NATURAL FEEDS & FOODS" INDUSTRIAL BUILDING, IN S.F.NO.323/C2, POWER LOAD 85HP, AND EXISTING APPROVED BUILDING OF A.C SHEET ROOF "M/s. MAHENDRA NATURAL FEEDS & FOOD MILL" (APPROVED NUMBER:28/2016), IN S.F.NO: 323/B, POWER LOAD 125 HP AT BOMMAMPATTI VILLAGE / PANCHAYAT, ELACHIPPALAYAM UNION, TIRUCHENGODE TALUK, NAMAKKAL DISTRICT.

APPLICANT:
"MAHENDRA NATURAL FEEDS & FOODS"
1.Mr.P.THILAGAM,W/O M.P.PALANISAMY
2.Mr.S.SUDHA,W/O M.SAKTHIVEL.



SITE APPROVAL
Roc.No. SWP/BPA/093018/2023
Site Boundary Shown as "A" to "L" and
Numbered as SWP/DTCP/NAMAKKAL/
Site Approval No: /2024

PLANNING PERMISSION
Roc.No. SWP/BPA/093018/2023
Planning Permission No: /2024

APPLICANT:

STRUCTURAL:

ENGINEER:

Per Mahendra Natural Feeds and Foods,
M/s. Mahendra Natural Feeds and Foods,
S. S. S. S.

M. P. P. P.
M. P. P. P.
M. P. P. P.

M. S. S. S.
M. S. S. S.
M. S. S. S.






Signature valid

Signed by: Director
Location: null
Date: 2024.09.24 16:25:39

Signature Not Verified
Signed by: Director
Location: null
Date: 2024.09.24 16:25:39

Signature Not Verified
Signed by: Director
Location: null
Date: 2024.09.24 16:25:39



AREA DETAILS:				ALL DIMENSIONS ARE IN METER				
AS PER PATTA		= 17035.00 SQ.MT						
AS PER DOCUMENT		= 17306.16 SQ.MT						
AS PER SUPER IMPOSED SITE AREA		= 17072.65 SQ.MT						
AS PER NAMAKKAL REGIONAL DEPUTY DIRECTOR (APPROVED NO.28/2016, DATED : 17.03.2016, S.F.NO.323/B) ALREADY APPROVED FSI AREA= 2241.43 Sq.m (BLOCK - 1)								
DESCRIPTION		TOTAL AREA						
		FSI		NON FSI		DEDUCTION		TOTAL BUILDUP AREA
BLOCK - 1 (EXISTING ALREADY APPROVED)								
GROUND FLOOR PLAN		2241.43		-		-		2241.43
TOTAL AREA - (A)		2241.43		-		-		2241.43
EXISTING BUILDING TO BE APPROVED								
DESCRIPTION		TOTAL AREA						
		FSI		NON FSI		DEDUCTION		TOTAL BUILDUP AREA
BLOCK - 2 (MACHINERY HALL)								
GROUND FLOOR PLAN (AC SHEET ROOF)		3123.90		-		-		3123.90
BLOCK - 3 (OFFICE ROOM)								
GROUND FLOOR PLAN (RCC ROOF)		114.84		-		-		114.84
FIRST FLOOR PLAN (RCC ROOF)		114.84		-		-		114.84
SECOND FLOOR PLAN (AC SHEET ROOF)		114.84		-		-		114.84
BLOCK - 4 (STORE ROOM)								
GROUND FLOOR PLAN (RCC ROOF)		111.80		-		-		111.80
BLOCK - 5 (CANTEN BLOCK)								
GROUND FLOOR PLAN (RCC ROOF)		68.78		-		-		68.78
FIRST FLOOR PLAN (RCC ROOF)		71.85		-		-		71.85
POWER ROOM								
GROUND FLOOR PLAN (RCC ROOF)		168.84		-		-		168.84
TOTAL AREA - (B)		3889.69		-		-		3889.69
EXISTING ALREADY APPROVED - A		2241.43		-		-		2241.43
EXISTING BUILDING TO BE APPROVED - B		3889.69		-		-		3889.69
GRAND TOTAL - A + B		6131.12		-		-		6131.12
FLOOR SPACE INDEX		TOTAL FSI AREA SITE AREA		= 6131.12 = 17024.98		= 0.36 < 1.5		
OPEN SPACE RESERVATION (10%) = 1738.57sq.m(10.04%)								
OSR BOUNDARY SHOWN AS [TO 4]								
PARKING DETAILS		REQUIRED		PROVIDED				
LORRY PARKING		12		12				
CAR PARKING		4		4				
PH CAR PARKING		2		2				
TWO WHEELER PARKING		114		115				
PH TWO WHEELER PARKING		7		7				
CYCLE PARKING		114		120				
PARKING AREA								
NOS OF LORRY PARKING = 12 NOS								
LORRY PARKING SIZE = 5.75M x 10.00M								
NOS OF CAR PARKING = 4 NOS								
CAR PARKING SIZE = 2.50M x 5.00M								
NOS OF PH CAR PARKING = 2 Nos								
PH CAR PARKING SIZE = 3.60M x 5.00M								
NOS OF TWO WHEELER PARKING = 115 NOS								
TWO WHEELER PARKING SIZE = 1.00M x 1.80M								
NOS OF PH TWO WHEELER PARKING = 7 Nos								
TWO WHEELER PARKING SIZE = 1.00M x 1.80M								
NOS OF CYCLE PARKING = 120 Nos								
CYCLE PARKING SIZE = 0.56M x 1.80M								