Verified RealEstate™

RE REGULATORY RECORD

RERA Document

The document as the regulator published it, reproduced in full behind this page.

Published for reference. The authority's own register is the operative record.

Verified RealEstate™
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India

hello@verified.realestate
+91 9996 12 9996
verified.realestate

DIGITALLY VERIFIED RECORD

C.KANNAN, M.E. (Structure)
STRUCTURAL ENGINEER

Door .21, plot No. 257- W, Flat No. 2B
"Utopia Apartments" 2nd Floor,
4th Main Road, Indira Nagar,
Chennai- 600 020
Mobile: 9841249815
Email: kannankds2007@gmail.com

21-07-2025

STRUCTURAL STABILITY CERTIFICATE

It is certified that the Proposed Residential Building of Stilt+Five Floors at Plot NO:15 & 16, Door NO:18(136) Friends Avenue, Arumbakkam, Chennai-600106, Comprised in Old S.NO.158,159,160/1,160/2,161, AND T.S NO:23/24, BLOCK NO:15, Ward-01 of Arumbakkam Village Within The Limits of Greater Chennai Corporation. Stilt plus Five upper floors is designed to resist earthquake. Check has been made and found safe and I hereby certify that,

1. The minimum column width is 300 in stilt floor
2. areas
3. The minimum grade of concrete is M25.
4. The design analysis using the code of practice for loading Standards as per IS-875 Part I to III and seismic force as per one code IS 1893, is carried out.

The Structure is safe and sound when used for the purpose for which it is designed.

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.

3.0 SOIL DETAILS

Based on soil test report Isolated foundation is adopted.

DESIGN METHODS

General design and detailing of concrete members/elements are done conforming to the provisions of I.S: 456 and other relevant I.S codes. Limit State method is followed for the design.

Seismic Zone III load is taken into account for the analysis. The predominant direction of vibration is horizontal. Relevant combination of forces has been taken into account.

4.1

Load Combination	Ultimate Limit Load	Serviceability Limit State
DL+LL+WL Or DL+LL+EL	1.2DL+1.2LL+1.2WL Or 1.2DL+1.2LL+1.2EL	DL+LL+WL or DL+LL+EL

4.3 **MINIMUM COVER**

Slab	15 mm
Beam	25 mm
Columns	40 mm
Foundations	50 mm

The Structure is safe and sound when used for the purpose for which it is designed.

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.

PROPOSED RESIDENTIAL BUILDING OF STILT+FIVE FLOORS AT PLOT NO:15 & 16, DOOR NO:18(136) FRIENDS AVENUE, ARUMBAKKAM, CHENNAI-600106, COMPRISED IN OLD S.NO.158,159,160/1,160/2,161, AND T.S NO:23/24, BLOCK NO:15, WARD-01 OF ARUMBAKKAM VILLAGE WITHIN THE LIMITS OF GREATER CHENNAI CORPORATION.

GENERAL NOTE ON STRUCTURAL DESIGN.

1.0 GENERAL.

1.1 DESIGN BASIS

The proposed residential building consists of stilt plus five upper floors.

The design of this building is carried out based on frame analysis using STAAD CONNECT.

1.2 CODES AND STANDARDS

All structural design is carried out conforming to the provisions of National Building Code of India and other relevant Indian Codes and Standards.

1. I.S. 456 - 2000
2. I.S. 875 - Part I to III
3. I.S.1893 - 2016

2.0 BASIC CIVIL DESIGN LOADS

2.1 DEAD LOADS & LIVE LOADS

Typical slab dead load is calculated as follows

Self weight of slab	=	3.25kN/m²
Floor finish	=	2.0kN/m²
Live load	=	2.0kN/m²
		7.25kN/m²

C. KANNAN, B.E.,M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.

```
**************************************************
*                                                *
*          STAAD.Pro 2024                        *
*          Version  24.00.02.354                 *
*          Proprietary Program of                *
*          Bentley Systems, Inc.                 *
*          Date=    JUL 21, 2025                 *
*          Time=    12:58: 1                     *
*                                                *
*  Licensed to: C.Kannan                         *
**************************************************
```

```
    1. STAAD SPACE DXF IMPORT OF UNTITLED1
INPUT FILE: D:\LOGESH\STABILITY CERTIFICATE\PUSHKAR - ARUMBAKKAM\PUSHAKR-ARUMBAKKAM_T[1]_21.07.2025.STD
    2. START JOB INFORMATION
    3. ENGINEER DATE 21-JUL-25
    4. JOB NAME PROPOSED RESIDENTIAL BUILDING OF STILT+FIVE FLOORS AT PLOT NO:15 & -
    5. 16, DOOR NO:18(136) FRIENDS AVENUE, ARUMBAKKAM, CHENNAI-600106, COMPRISED IN -
    6. OLD S.NO.158,159,160/1,160/2,161, AND T.S NO:23/24, BLOCK NO:15, WARD-01 OF -
    7. ARUMBAKKAM VILLAGE WITHIN THE LIMITS OF GREATER CHENNAI CORPORATION
    8. ENGINEER NAME KANNAN
    9. CHECKER NAME KANNAN
   10. APPROVED NAME KANNAN
   11. CHECKER DATE 7/21/2025
   12. APPROVED DATE 7/21/2025
   13. END JOB INFORMATION
   14. INPUT WIDTH 79
   15. UNIT INCHES KN
   16. JOINT COORDINATES
   17. 1 0 0 0; 6 227.52 0 0; 7 368.5 0 0; 8 509.5 0 0; 9 735.999 0 0; 10 0 118.11 0
   18. 11 227.52 118.11 0; 12 368.5 118.11 0; 13 509.5 118.11 0; 14 735.999 118.11 0
   19. 15 0 236.22 0; 16 227.52 236.22 0; 17 368.5 236.22 0; 18 509.5 236.22 0
   20. 19 735.999 236.22 0; 20 0 354.331 0; 21 227.52 354.331 0; 22 368.5 354.331 0
   21. 23 509.5 354.331 0; 24 735.999 354.331 0; 25 0 472.441 0; 26 227.52 472.441 0
   22. 27 368.5 472.441 0; 28 509.5 472.441 0; 29 735.999 472.441 0; 30 0 590.551 0
   23. 31 227.52 590.551 0; 32 368.5 590.551 0; 33 509.5 590.551 0
   24. 34 735.999 590.551 0; 35 0 708.661 0; 36 227.52 708.661 0; 37 368.5 708.661 0
   25. 38 509.5 708.661 0; 39 735.999 708.661 0; 40 0 -118.11 0; 41 227.52 -118.11 0
   26. 42 368.5 -118.11 0; 43 509.5 -118.11 0; 44 735.999 -118.11 0
   27. MEMBER INCIDENCES
   28. 5 1 6; 6 6 7; 7 7 8; 8 8 9; 9 1 10; 10 6 11; 11 7 12; 12 8 13; 13 9 14
   29. 14 10 11; 15 11 12; 16 12 13; 17 13 14; 18 10 15; 19 11 16; 20 12 17; 21 13 18
   30. 22 14 19; 23 15 16; 24 16 17; 25 17 18; 26 18 19; 27 15 20; 28 16 21; 29 17 22
   31. 30 18 23; 31 19 24; 32 20 21; 33 21 22; 34 22 23; 35 23 24; 36 20 25; 37 21 26
   32. 38 22 27; 39 23 28; 40 24 29; 41 25 26; 42 26 27; 43 27 28; 44 28 29; 45 25 30
   33. 46 26 31; 47 27 32; 48 28 33; 49 29 34; 50 30 31; 51 31 32; 52 32 33; 53 33 34
   34. 54 30 35; 55 31 36; 56 32 37; 57 33 38; 58 34 39; 59 35 36; 60 36 37; 61 37 38
   35. 62 38 39; 63 40 1; 64 41 6; 65 42 7; 66 43 8; 67 44 9
   36. UNIT METER KN
   37. DEFINE MATERIAL START
   38. ISOTROPIC CONCRETE
```

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.

```
39. E 2.17185E+07
40. POISSON 0.17
41. DENSITY 23.5616
42. ALPHA 1E-05
43. DAMP 0.05
44. G 9.28139E+06
45. TYPE CONCRETE
46. STRENGTH FCU 27579
47. END DEFINE MATERIAL
48. MEMBER PROPERTY
49. 5 TO 8 14 TO 17 23 TO 26 32 TO 35 41 TO 44 50 TO 53 59 TO 61 -
50. 62 PRIS YD 0.45 ZD 0.23
51. 9 TO 13 18 TO 22 27 TO 31 36 TO 40 45 TO 49 54 TO 58 63 TO 66 -
52. 67 PRIS YD 0.45 ZD 0.23
53. CONSTANTS
54. MATERIAL CONCRETE ALL
55. UNIT INCHES KN
56. SUPPORTS
57. 40 TO 44 FIXED
58. UNIT METER KN
59. DEFINE IS1893 2016 LOAD
60. ZONE 0.16 RF 5 I 1.2 SS 1 ST 1 DM 0.05 DT 3
61. SELFWEIGHT 1
62. MEMBER WEIGHT
63. 5 TO 8 14 TO 17 23 TO 26 32 TO 35 41 TO 44 50 TO 53 59 TO 62 UNI 12 0 0
64. 5 TO 8 14 TO 17 23 TO 26 32 TO 35 41 TO 44 50 TO 53 59 TO 62 UNI 30 0 0
65. DEFINE WIND LOAD

*** NOTE: If any floor diaphragm is present in the model Wind Load definition
          should be defined after Floor Diaphragm definition. Otherwise wind
          load generation may be unsuccessful during analysis.

66. TYPE 1 WIND 1
67. <! STAAD PRO GENERATED DATA DO NOT MODIFY !!!
68. CUSTOM:PARAMS
69. !> END GENERATED DATA BLOCK
70. INT 1.35 1.49 1.65 HEIG  10  15  18
71. EXP 1 JOINT 1 6 TO 44
72. LOAD 1 LOADTYPE NONE  TITLE EQ +X
73. 1893 LOAD X 1
74. LOAD 2 LOADTYPE NONE  TITLE EQ -X
75. 1893 LOAD X -1.
76. LOAD 3 LOADTYPE NONE  TITLE EQ +Z
77. 1893 LOAD Z 1
78. LOAD 4 LOADTYPE NONE  TITLE EQ -Z
79. 1893 LOAD Z -1.
```

DXF IMPORT OF UNTITLED1 -- PAGE NO. 3

```
  80. LOAD 5 LOADTYPE NONE  TITLE WIND +X
  81. WIND LOAD X 1 TYPE 1
*WARNING- NO MEMBERS LOADED FOR A WIND LOAD GENERATION.
  82. LOAD 6 LOADTYPE NONE  TITLE WIND -X
  83. WIND LOAD -X 1 TYPE 1
*WARNING- NO MEMBERS LOADED FOR A WIND LOAD GENERATION.
  84. LOAD 7 LOADTYPE NONE  TITLE WIND +Z
  85. WIND LOAD Z 1 TYPE 1
  86. LOAD 8 LOADTYPE NONE  TITLE WIND -Z
  87. WIND LOAD -Z 1 TYPE 1
  88. LOAD 9 LOADTYPE NONE  TITLE LL
  89. MEMBER LOAD
  90. 5 TO 8 14 TO 17 23 TO 26 32 TO 35 41 TO 44 50 TO 53 59 TO 62 UNI GY -12
  91. LOAD 10 LOADTYPE NONE  TITLE DL
  92. SELFWEIGHT Y -1
  93. MEMBER LOAD
  94. 5 TO 8 14 TO 17 23 TO 26 32 TO 35 41 TO 44 50 TO 53 59 TO 62 UNI GY -30
  95. LOAD COMB 11 1.5(DL+IL)
  96. 9 1.5 10 1.5
  97. LOAD COMB 12 1.2(DL+IL+ELX)
  98. 9 1.5 10 1.2 1 1.2
  99. LOAD COMB 13 1.2(DL+IL-ELX)
 100. 9 1.2 10 1.2 2 1.2
 101. LOAD COMB 14 1.2(DL+IL+ELZ)
 102. 9 1.2 10 1.2 3 1.2
 103. LOAD COMB 15 1.2(DL+IL-ELZ)
 104. 9 1.2 10 1.2 4 1.2
 105. LOAD COMB 16 1.2(DL+IL+WLX)
 106. 9 1.2 10 1.2 5 1.2
 107. LOAD COMB 17 1.2(DL+IL-WLX)
 108. 10 1.2 6 1.2
 109. LOAD COMB 18 1.2(DL+IL+WLZ)
 110. 9 1.2 10 1.2 7 1.2
 111. LOAD COMB 19 1.2(DL+IL-WLZ)
 112. 9 1.2 10 1.2 8 1.2
 113. LOAD COMB 20 1.5(DL+ELX)
 114. 9 1.5 10 1.5 1 1.5
 115. LOAD COMB 21 1.5(DL-ELX)
 116. 9 1.5 10 1.5 2 1.5
 117. LOAD COMB 22 1.5(DL+ELZ)
 118. 9 1.5 10 1.5 3 1.5
```

DXF IMPORT OF UNTITLED1 -- PAGE NO. 4

```
119. LOAD COMB 23 1.5(DL-ELZ)
120. 10 1.5 4 1.5
121. LOAD COMB 24 1.5(DL+WLX)
122. 10 1.5 5 1.5
123. LOAD COMB 25 1.5(DL-WLX)
124. 10 1.5 6 1.5
125. LOAD COMB 26 1.5(DL+WLZ)
126. 10 1.5 7 1.5
127. LOAD COMB 27 1.5(DL-WLZ)
128. 10 1.5 8 1.5
129. LOAD COMB 28 0.9 DL+ELX
130. 10 0.9 1 1.5
131. LOAD COMB 29 0.9 DL-ELX
132. 10 0.9 2 1.5
133. LOAD COMB 30 0.9 DL+ELZ
134. 10 0.9 3 1.5
135. LOAD COMB 31 0.9 DL-ELZ
136. 10 0.9 4 1.5
137. LOAD COMB 32 0.9 DL+WLX
138. 10 0.9 5 1.5
139. LOAD COMB 33 0.9 DL-WLX
140. 10 0.9 6 1.5
141. LOAD COMB 34 0.9 DL+WLZ
142. 10 0.9 7 1.5
143. LOAD COMB 35 0.9 DL-WLZ
144. 10 0.9 8 1.5
145. PERFORM ANALYSIS PRINT ALL
```

P R O B L E M S T A T I S T I C S

NUMBER OF JOINTS	40	NUMBER OF MEMBERS	63
NUMBER OF PLATES	0	NUMBER OF SOLIDS	0
NUMBER OF SURFACES	0	NUMBER OF SUPPORTS	5


Using 64-bit analysis engine.

SOLVER USED IS THE IN-CORE ADVANCED MATH SOLVER


TOTAL PRIMARY LOAD CASES = 10, TOTAL DEGREES OF FREEDOM = 210
TOTAL LOAD COMBINATION CASES = 25 SO FAR.

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.





C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.



7.119 kN
13.548 kN
12.858 kN
11.851 kN
11.650 kN
11.650 kN
11.650 kN
851 kN
477 kN
252 kN
451 kN
825 kN
Y
Z
X

Load 7

Bentley Software licensed to C.Kannan CONNECTED User: Kannan Chinnasamy	Job No	Sheet No 1	Rev
	Part		
Job Title Proposed Residential Building of Stilt+Five Floors at Plot NO:15 & 16, Door NO:18(136) Friends Avenue, Arumbakkam, Chennai-600106, Comprised in	Ref		
	By Kannan	Date 21-Jul-25	Chd Kannan
Client	File PUSHAKR-ARUMBAKKA	Date/Time 21-Jul-2025 12:58	




Print Time/Date: 21/07/2025 13:06 STAAD.Pro 2024 24.00.02.354 Print Run 1 of 1




Load 10


C.KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.




ALL SLABS ARE 5" TK UNLESS SPCIFIED




C.S OF FB1




C.S OF FB2




C.S OF FB3




C.S OF FB4




L.S OF FB5




C.S OF FB5




C.S OF FB6







L.S OF FB7




C.S OF FB7




L.S OF CB1 L.S OF FB8




C.S OF FB8




C.S OF CB1




L.S OF FB9




C.S OF FB9




C.S OF FB23




L.S OF FB11 L.S OF FB10




C.S OF FB10




C.S OF FB11




L.S OF FB12 L.S OF FB13




C.S OF FB12 C.S OF FB13




L.S OF FB14 L.S OF FB15




C.S OF FB14




C.S OF FB15




TYP. SEC. FOR STP. DETAILS




L.S OF FB16 L.S OF FB17 L.S OF FB18




C.S OF FB16




C.S OF FB17




C.S OF FB18




L.S OF FB20 L.S OF FB19




C.S OF FB19




C.S OF FB20



L.S OF FB21



C.S OF FB21



C.S OF FB22
(BELOW SUNKEN)

Notes:-

1. This drawing should be read along with architectural drawings.
2. Grade of R.C.C. items shall be M30 for column & M25 for all other R.C.C works
3. Y Denotes TOR50 Steel confirming to I.S. 1786 – 1985. Grade – Fe 500
4. Clear cover to the main steel
   50 for Footings , Raft Slabs & Raft Beams.
   40 for Columns.
   25 for Lintel & Beams.
   20 for Sunshade & Slab.
5. Lap length shall be 50 d (Max. dia) for all bars.
6. ——— Bottom Reinforcement
7. ----- Top Reinforcement
8. Provide Continuous Chairs to keep the top Reinforcement in position
9. Provide Y 8 at 200 as Distribution steel for all top Reinforcement.
10. Spacer Bar to be Provided in Between Two Layers Of Reinforcement of Same Dia at Every 1000 C/ C.
11. Not more than 40% of Reinforcement shall be Lapped at any particular junction.
12. Cantilever props should not be released until the roof is concreted.
13. Foundation is designed for Stilt plus Five upper floor only.
14. For Earthquake analysis Zone III is taken as per IS : 1893–2016 code.
15. Removal of formworks :
    i) For Slabs :
    a. Slabs spanning upto 4.5 m (15'-0") – 7 days
    b. Slabs spanning over 4.5 m (15'-0") – 14 days
    ii) For Beams and Arches :
    c. Beams and Arches spanning upto 6 m (20'-0") –14days
    d. Beams and Arches spanning over 6 m (20'-0") –21days

R.NO	DATE	DESCRIPTION

PROJECT

PROPOSED RESIDENTIAL BUILDING OF STILT+FIVE FLOORS AT PLOT NO:15 & 16, DOOR NO:18(136) FRIENDS AVENUE, ARUMBAKKAM, CHENNAI–600106, COMPRISED IN OLD S.NO.158,159,160/1, 160/2,161, AND T.S NO:23/24, BLOCK NO:15, WARD–01 OF ARUMBAKKAM VILLAGE WITHIN THE LIMITS OF GREATER CHENNAI CORPORATION.

TYPICAL FLOOR ROOF DETAIL


DESIGNED	KANNAN	SCALE	1 : 100
DRAWN	NASURTHEEN	DATE	21-07-2025


STRUCTURAL CONSULTANTS:

C.KANNAN B.E., M.E.(STRUCTURE)
DOOR NO:21, PLOT NO:257–W,
FLAT NO:2B, "UTOPIA APARTMENTS",
2nd FLOOR, 4th MAIN ROAD,
INDIRA NAGAR, CHENNAI–20.
MOBILE NO: 098412 49815.
E–MAIL:kannonkds2007@gmail.com


FILE NAME : D:\NASURTHEEN\2025\PRISHKAR–ARUMBAKKAM

C. KANNAN, B.E., M.E. (Structure)
Consulting Engineer,
Regd. No: SE/1/2024/2/0047
No. 3, Vijaya Nagar, Chennai-600 020.







COL-C1




COL-C2




COL-F1




COL-F2




COL-F3




COL-F4




COL-F5




COL-F6




COL-F7




FOOTING-F1&F6




FOOTING-F2,F7




FOOTING-F3




FOOTING-F4




FOOTING-F5




C.S OF TB1




C.S OF TB2




L.S OF TB3




C.S OF TB3




L.S OF TB4




C.S OF TB4




LIFTWELL SECTION




TYP.FOUNDATION



TYP. SEC. FOR STP. DETAILS



L.S OF TB5



C.S OF TB5

Notes:-

1. This drawing should be read along with architectural drawings.
2. Grade of R.C.C. items shall be M30 for column & M25 for all other R.C.C works
3. Y Denotes TOR50 Steel confirming to I.S. 1786 – 1985. Grade – Fe 500
4. Clear cover to the main steel
   50 for Footings , Raft Slabs & Raft Beams.
   40 for Columns.
   25 for Lintel & Beams.
   20 for Sunshade & Slab.
5. Lap length shall be 50 d (Max. dia) for all bars.
6. ——— Bottom Reinforcement
7. ------ Top Reinforcement
8. Provide Continuous Chairs to keep the top Reinforcement in position
9. Provide Y 8 at 200 as Distribution steel for all top Reinforcement.
10. Spacer Bar to be Provided in Between Two Layers Of Reinforcement of Same Dia at Every 1000 C/ C.
11. Not more than 40% of Reinforcement shall be Lapped at any particular junction.
12. Cantilever props should not be released until the roof is concreted.
13. Foundation is designed for Stilt plus Five upper floor only.
14. For Earthquake analysis Zone III is taken as per IS : 1893-2016 code.
15. Removal of formworks :
    i) For Slabs :
    a. Slabs spanning upto 4.5 m (15'-0") – 7 days
    b. Slabs spanning over 4.5 m (15'-0") – 14 days
    ii) For Beams and Arches :
    c. Beams and Arches spanning upto 6 m (20'-0") –14days
    d. Beams and Arches spanning over 6 m (20'-0") –21days

R.NO	DATE	DESCRIPTION

PROJECT

PROPOSED RESIDENTIAL BUILDING OF STILT+FIVE FLOORS AT PLOT NO:15 & 16, DOOR NO:18(136) FRIENDS AVENUE, ARUMBAKKAM, CHENNAI-600106, COMPRISED IN OLD S.NO.158,159,160/1, 160/2,161, AND T.S NO:23/24, BLOCK NO:15, WARD-01 OF ARUMBAKKAM VILLAGE WITHIN THE LIMITS OF GREATER CHENNAI CORPORATION.

FOUNDATION DETAIL

DESIGNED	KANNAN		SCALE	1 : 100
DRAWN	NASURTHEEN		DATE	21-07-2025

STRUCTURAL CONSULTANTS:

C.KANNAN B.E., M.E(STRUCTURE)., M.E. (Structure)
Structural Engineer, SE/1/2024/2/0047
Flat No: 21, 4th Main Road, Indira Nagar, Chennai-600 020.
DOOR NO:21, PLOT NO:297-W,
FLAT NO:2B, "UTOPIA APARTMENTS",
2nd FLOOR, 4th MAIN ROAD,
INDIRA NAGAR, CHENNAI-20.
MOBILE NO: 098412 49815.
E-MAIL:kannanks2007@gmail.com

FILE NAME : D/NASURTHEEN/JULY25/PUSHKAR-ARUMBAKKAM

THE LANDLENS SUITE

Eight ways to know a piece of land before you pay for it.

This report covers one part of the picture. These cover the rest, drawn from the same government records, for any property in Tamil Nadu.

LandLens One
Ask anything about a property and get an answer grounded in live government records, with the sources shown.
/landlens/one

Verify My Land
Every record check run on one property and returned as a single report.
/landlens/verify-my-land

Legal Opinion
An advocate's written opinion on the title, built on the records we pull for it.
/landlens

One Map
Every layer on one map: the parcel, its boundary, zoning, water bodies and what sits around it.
/landlens/one/map

PriceMap
What land actually changed hands for around this plot, taken from the registered deeds.
/landlens/pricemap

Build Scope
What you are allowed to build here: floor space, height, coverage and setbacks.
/landlens/build-scope

Property Tracker
Watch a property and hear about it when something new is registered against it.
/landlens/property-tracker

Deal Room
Run the transaction in one place: documents, stamping, signatures and the parties.
/landlens/deal-room

FREE TOOLS · NO ACCOUNT NEEDED

Twenty-four checks you can run yourself, at no cost.

Records and verification

The registers themselves, read for you.

- Encumbrance Certificate
- Patta and Chitta
- Field Measurement Sketch
- EC Analyzer
- Bank charge check
- Court case search
- Seller background check
- Approval check by survey

Value and duty

What it is worth and what it costs to register.

- Guideline value by street
- Guideline value by survey
- Stamp duty and registration fees
- Capital gains
- Floor space index
- Area unit converter

Zoning and land use

What the plan says can happen on this land.

- Land use zone finder
- CMDA land use check
- Coastal regulation zone
- Master plan check
- Water bodies finder
- Airport height clearance

Registers and directories

Who holds it, and which office keeps the record.

- Find your registering office
- Temple property check
- Waqf property check
- RERA register

Every free tool
/tools

Services we run for you
/services

The LandLens suite
/landlens/one

Verified RealEstate™

Every claim in this document traces back to a government record.

- Legal opinions, due diligence and title verification
- Building plan, layout and sub-division approvals
- Completion and occupancy certificates, regularisation
- Escrow, negotiation and NRI property management
- Land survey, soil testing, architecture and construction

Verified RealEstate
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India
hello@verified.realestate
+91 9996 12 9996

Prepared from the registers named on the page each finding sits on. Where a register could not be read, this document says so in its place rather than leaving the gap to be read as a clean result.