Verified RealEstate™

Your trusted partner for buying, selling, and managing property, ensuring hassle-free service with 100% transparency.

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai, India

hello@verified.realestate
+91 9996 12 9996

Official Property Record

Digitally Verified Record - Powered by Verified RealEstate™



CHENNAI METROPOLITAN DEVELOPMENT AUTHORITY
Thalamuthu Natarajan Building, No.1, Gandhi Irwin Road, Egmore,
Chennai - 600 008
Phone : 28414855 Fax: 91-044-28548416
E-mail: mscmda@tn.gov.in
Web site: www.cmdachennai.gov.in.

PROFESSIONAL REGISTRATION CERTIFICATE

This is to certify that the Thiru / Tmt. / M/s. **C.KANNAN** has enrolled as **Registered Structural Engineer Grade-I(SE)** with Chennai Metropolitan Development Authority (CMDA) who has the qualification of **M.E Structures** and experience in the relevant field for **15** years.

He/She has been given the Registration No. **SE/I/2024/2/0047** on **28-Feb-2024** He/She shall be required to comply with the duties and responsibilities prescribed by the Government of Tamil Nadu in Part V, “Registration of Professionals”, Tamil Nadu Combined Development and Building Rules, 2019 approved vide G.O.(ms) No.18 MAWS (MA1) Dept. Dated. 04.02.2019.

This Registration is valid upto **27-Feb-2029**.

Signature Not Verified
Name :A Meganathan
Designation :Superintendent
Date :02/28/2024 12:50:37 PM



A Meganathan

Superintendent

C.KANNAN, M.E. (Structure)
STRUCTURAL ENGINEER

Door .21, plot No. 257- W, Flat No. 2B
"Utopia Apartments" 2nd Floor,
4th Main Road, Indira Nagar,
Chennai- 600 020
Mobile: 9841249815
Email: kannankds2007@gmail.com

15-11-2024

STRUCTURAL STABILITY CERTIFICATE

It is certified that the Proposed Residential Building at Door No:E-1 To E-6, Block –E, 54th Street/56th Street, Ashok Nagar, Chennai-600083, Comprised In Old S.No:220 Part, T.S No:2, Block No:72 Of Kodambakkam Village Within The Limits Of Greater Chennai Corporation. Old Division:132, New Division:135, Zone:10.Having Stilt plus Five upper floors is designed to resist earthquake. Check has been made safe and sound, I hereby certify that,

1. The minimum column width is 300 in stilt floor areas
2. The minimum grade of concrete is M25.
3. The design analysis using the code of practice for loading Standards as per IS-875 Part I to III and seismic force as per one code IS 1893, is carried out.

The Structure is safe and sound when used for the purpose for which it is designed.

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.

PROPOSED RESIDENTIAL BUILDING AT DOOR NO:E-1 TO E-6, BLOCK –E, 54TH STREET/56TH STREET, ASHOK NAGAR, CHENNAI-600083, COMPRISED IN OLD S.NO:220 PART, T.S NO:2, BLOCK NO:72 OF KODAMBAKKAM VILLAGE WITHIN THE LIMITS OF GREATER CHENNAI CORPORATION. OLD DIVISION:132, NEW DIVISION:135, ZONE:10.

GENERAL NOTE ON STRUCTURAL DESIGN.

1.0 GENERAL.

1.1 DESIGN BASIS

The proposed residential building consists of Stilt plus Five upper floors.

The design of this building is carried out based on frame analysis using STAAD CONNECT.

1.2 CODES AND STANDARDS

All structural design is carried out conforming to the provisions of National Building Code of India and other relevant Indian Codes and Standards.

1. I.S. 456 - 2000
2. I.S. 875 - Part I to III
3. I.S.1893 - 2016

2.0 BASIC CIVIL DESIGN LOADS

2.1 DEAD LOADS & LIVE LOADS

Typical slab dead load is calculated as follows

Self weight of slab	=	3.25kN/m²
Floor finish	=	2.0kN/m²
Live load	=	2.0kN/m²
		7.25kN/m²

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.

3.0 SOIL DETAILS

Based on soil test report shallow Foundation is adopted.

DESIGN METHODS

General design and detailing of concrete members/elements are done conforming to the provisions of I.S: 456 and other relevant I.S codes. Limit State method is followed for the design.

Seismic Zone III load is taken into account for the analysis. The predominant direction of vibration is horizontal. Relevant combination of forces has been taken into account.

4.1

Load Combination	Ultimate Limit Load	Serviceability Limit State
DL+LL+WL Or DL+LL+EL	1.2DL+1.2LL+1.2WL Or 1.2DL+1.2LL+1.2EL	DL+LL+WL or DL+LL+EL

4.3 **MINIMUM COVER**

Slab	15 mm
Beam	25 mm
Columns	40 mm
Foundations	50 mm

The Structure is safe and sound when used for the purpose for which it is designed.

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.

```
**************************************************
*                                                *
*           STAAD.Pro CONNECT Edition            *
*           Version  22.12.00.142                *
*           Proprietary Program of               *
*           Bentley Systems, Inc.                *
*           Date=    NOV 15, 2024                *
*           Time=    17:11: 4                    *
*                                                *
*  Licensed to: C.Kannan                         *
**************************************************
```

```
     1. STAAD SPACE
INPUT FILE: D:\AGAN\4.STABILITY\Pushkar -Ashok Nagar\Staad\Pushkar - As.. .STD
     2. START JOB INFORMATION
     3. ENGINEER DATE 15-NOV-24
     4. JOB NAME PROPOSED RESIDENTIAL BUILDING AT DOOR NO:E-1 TO E-6, BLOCK -E, 54TH -
     5. STREET/56TH STREET, ASHOK NAGAR, CHENNAI-600083
     6. ENGINEER NAME KANNAN
     7. CHECKER NAME KANNAN
     8. APPROVED NAME KANNAN
     9. CHECKER DATE 11/15/2024
    10. APPROVED DATE 11/15/2024
    11. END JOB INFORMATION
    12. INPUT WIDTH 79
    13. SET NL 250
    14. UNIT INCHES KN
    15. JOINT COORDINATES
    16. 1 0 0 0; 2 327 0 0; 3 0 118.11 0; 4 327 118.11 0; 5 0 236.22 0; 6 327 236.22 0
    17. 7 0 354.331 0; 8 327 354.331 0; 9 0 472.441 0; 10 327 472.441 0
    18. 11 0 590.551 0; 12 327 590.551 0; 13 0 708.661 0; 14 327 708.661 0
    19. 15 0 -78.7402 0; 16 327 -78.7402 0
    20. MEMBER INCIDENCES
    21. 1 1 2; 2 3 4; 3 5 6; 4 7 8; 5 9 10; 6 11 12; 7 13 14; 8 15 1; 9 1 3; 10 3 5
    22. 11 5 7; 12 7 9; 13 9 11; 14 11 13; 15 16 2; 16 2 4; 17 4 6; 18 6 8; 19 8 10
    23. 20 10 12; 21 12 14
    24. UNIT METER KN
    25. DEFINE MATERIAL START
    26. ISOTROPIC CONCRETE
    27. E 2.17185E+07
    28. POISSON 0.17
    29. DENSITY 23.5616
    30. ALPHA 1E-05
    31. DAMP 0.05
    32. G 9.28139E+06
    33. TYPE CONCRETE
    34. STRENGTH FCU 27579
    35. END DEFINE MATERIAL
    36. MEMBER PROPERTY
    37. 8 TO 21 PRIS YD 0.45 ZD 0.23
    38. 1 TO 7 PRIS YD 0.45 ZD 0.23
```

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.

STAAD SPACE -- PAGE NO. 2

```
  39. CONSTANTS
  40. MATERIAL CONCRETE ALL
  41. UNIT INCHES KN
  42. SUPPORTS
  43. 15 16 FIXED
  44. UNIT METER KN
  45. DEFINE WIND LOAD

 *** NOTE: If any floor diaphragm is present in the model Wind Load definition
           should be defined after Floor Diaphragm definition. Otherwise wind
           load generation may be unsuccessful during analysis.

  46. TYPE 1 WIND 1
  47. <! STAAD PRO GENERATED DATA DO NOT MODIFY !!!
  48. CUSTOM:PARAMS
  49. !> END GENERATED DATA BLOCK
  50. INT 1.22 1.35 1.48 HEIG  10  15  18
  51. EXP 1 JOINT 1 TO 16
  52. DEFINE IS1893 2016 LOAD
  53. ZONE 0.16 RF 5 I 1.2 SS 1 ST 1 DM 0.05 DT 2
  54. MEMBER WEIGHT
  55. 1 TO 7 UNI 12 0 0
  56. 1 TO 7 UNI 25 0 0
  57. SELFWEIGHT 1
  58. LOAD 1 LOADTYPE SEISMIC-H  TITLE EQX
  59. 1893 LOAD X 1
  60. LOAD 2 LOADTYPE SEISMIC-H  TITLE EQX
  61. 1893 LOAD X -1.
  62. LOAD 3 LOADTYPE SEISMIC-V  TITLE EQZ
  63. 1893 LOAD Z 1
  64. LOAD 4 LOADTYPE SEISMIC-V  TITLE EQZ
  65. 1893 LOAD Z -1.
  66. LOAD 5 LOADTYPE WIND  TITLE WIND +X
  67. WIND LOAD X 1 TYPE 1
*WARNING- NO MEMBERS LOADED FOR A WIND LOAD GENERATION.
  68. LOAD 6 LOADTYPE WIND  TITLE WIND -X
  69. WIND LOAD -X 1 TYPE 1
*WARNING- NO MEMBERS LOADED FOR A WIND LOAD GENERATION.
```

```
70. LOAD 7 LOADTYPE WIND  TITLE WIND +Z
71. WIND LOAD Z 1 TYPE 1
72. LOAD 8 LOADTYPE WIND  TITLE WIND -Z
73. WIND LOAD -Z 1 TYPE 1
74. LOAD 9 LOADTYPE LIVE  TITLE L.L
75. MEMBER LOAD
76. 1 TO 7 UNI GY -12
77. LOAD 10 LOADTYPE DEAD  TITLE D.L
78. SELFWEIGHT Y -1 LIST ALL
79. MEMBER LOAD
80. 1 TO 7 UNI GY -25
81. LOAD COMB 11 1.5(DL+IL)
82. 9 1.5 10 1.5
83. LOAD COMB 12 1.2(DL+IL+ELX)
84. 9 1.5 10 1.2 1 1.2
85. LOAD COMB 13 1.2(DL+IL-ELX)
86. 9 1.2 10 1.2 2 1.2
87. LOAD COMB 14 1.2(DL+IL+ELZ)
88. 9 1.2 10 1.2 3 1.2
89. LOAD COMB 15 1.2(DL+IL-ELZ)
90. 9 1.2 10 1.2 4 1.2
91. LOAD COMB 16 1.2(DL+IL+WLX)
92. 9 1.2 10 1.2 5 1.2
93. LOAD COMB 17 1.2(DL+IL-WLX)
94. 10 1.2 6 1.2
95. LOAD COMB 18 1.2(DL+IL+WLZ)
96. 9 1.2 10 1.2 7 1.2
97. LOAD COMB 19 1.2(DL+IL-WLZ)
98. 9 1.2 10 1.2 8 1.2
99. LOAD COMB 20 1.5(DL+ELX)
100. 9 1.5 10 1.5 1 1.5
101. LOAD COMB 21 1.5(DL-ELX)
102. 9 1.5 10 1.5 2 1.5
103. LOAD COMB 22 1.5(DL+ELZ)
104. 9 1.5 10 1.5 3 1.5
105. LOAD COMB 23 1.5(DL-ELZ)
106. 10 1.5 4 1.5
107. LOAD COMB 24 1.5(DL+WLX)
108. 10 1.5 5 1.5
109. LOAD COMB 25 1.5(DL-WLX)
110. 10 1.5 6 1.5
111. LOAD COMB 26 1.5(DL+WLZ)
112. 10 1.5 7 1.5
113. LOAD COMB 27 1.5(DL-WLZ)
114. 10 1.5 8 1.5
115. LOAD COMB 28 0.9 DL+ELX
116. 10 0.9 1 1.5
117. LOAD COMB 29 0.9 DL-ELX
118. 10 0.9 2 1.5
119. LOAD COMB 30 0.9 DL+ELZ
```

```
120. 10 0.9 3 1.5
121. LOAD COMB 31 0.9 DL-ELZ
122. 10 0.9 4 1.5
123. LOAD COMB 32 0.9 DL+WLX
124. 10 0.9 5 1.5
125. LOAD COMB 33 0.9 DL-WLX
126. 10 0.9 6 1.5
127. LOAD COMB 34 0.9 DL+WLZ
128. 10 0.9 7 1.5
129. LOAD COMB 35 0.9 DL-WLZ
130. 10 0.9 8 1.5
131. PERFORM ANALYSIS PRINT ALL
```

P R O B L E M S T A T I S T I C S

NUMBER OF JOINTS	16	NUMBER OF MEMBERS	21
NUMBER OF PLATES	0	NUMBER OF SOLIDS	0
NUMBER OF SURFACES	0	NUMBER OF SUPPORTS	2


Using 64-bit analysis engine.

SOLVER USED IS THE IN-CORE ADVANCED MATH SOLVER


TOTAL PRIMARY LOAD CASES = 10, TOTAL DEGREES OF FREEDOM = 84
TOTAL LOAD COMBINATION CASES = 25 SO FAR.




C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.




C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai - 600 020.


9.219 kN
17.629 kN
16.819 kN
15.470 kN
15.200 kN
15.200 kN
12.666 kN
.067 kN
.067 kN
Y
Z
X

Load 7


-12.000 kN/m
-12.000 kN/m
-12.000 kN/m
-12.000 kN/m
-12.000 kN/m
-12.000 kN/m
-12.000 kN/m
Y
Z
X


Load 9







Load 10

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai - 600 020.







COL-F1&C1




COL-C2




COL-C3




COL-F6&C4




COL-F2




COL-F3




COL-F4




COL-F5




FOOTING-F1&F2




FOOTING-F3




FOOTING-F4




FOOTING-F5&F6




COL-F7
(SECTION A A)




FOOTING-F7




FOOTING-CF1




FOOTING-CF2




C.S OF TB1




C.S OF TB2




L.S OF TB3




C.S OF TB3




L.S OF TB4




C.S OF TB4




LIFTWELL SECTION




TYP.FOUNDATION



L.S OF TB5



C.S OF TB5



TYP. SEC. FOR
STP. DETAILS

Notes:-

1. This drawing should be read along with architectural drawings.
2. Grade of R.C.C. items shall be M30 for column & M25 for all other R.C.C works
3. Y Denotes TOR40 Steel confirming to I.S. 1786 - 2008. Grade - Fe 500
4. Clear cover to the main steel
   - 50 for Footings , Raft Slabs & Raft Beams.
   - 40 for Columns.
   - 25 for Lintel & Beams.
   - 20 for Sunshade & Slab.
5. Lap length shall be 50 d (Max. dia) for all bars.
6. ——— Bottom Reinforcement
7. ----- Top Reinforcement
8. Provide Continuous Chairs to keep the top Reinforcement in position
9. Provide Y 8 at 200 as Distribution steel for all top Reinforcement.
10. Spacer Bar to be Provided in Between Two Layers Of Reinforcement of Same Dia at Every 1000 C/ C.
11. Not more than 40% of Reinforcement shall be Lapped at any particular junction.
12. Cantilever props should not be released until the roof is concreted.
13. Foundation is designed for Stilt plus five upper floor only.
14. For Earthquake analysis Zone III is taken as per IS : 1893-2016 code.
15. Removal of formworks :
    - i) For Slabs :
    - a. Slabs spanning upto 4.5 m (15'-0") - 7 days
    - b. Slabs spanning over 4.5 m (15'-0") - 14 days
    - ii) For Beams and Arches :
    - c. Beams and Arches spanning upto 6 m (20'-0") -14days
    - d. Beams and Arches spanning over 6 m (20'-0") -21days

R.NO	DATE	DESCRIPTION

PROJECT

PROPOSED RESIDENTIAL BUILDING AT DOOR NO:E-1 TO E-6, BLOCK-E, 54TH STREET/56TH STREET, ASHOK NAGAR, CHENNAI-600083. COMPRISED IN OLD S.NO:220 PART, T.S.NO:2, BLOCK NO:72 OF KODAMBAKKAM, VILLAGE WITHIN THE LIMITS OF GRETER CHENNAI CORPORATION. OLD DIVISION:132, NEW DIVISION:135, ZONE:10.

FOUNDATION DETAIL


DESIGNED	KANNAN		SCALE	1 : 100
DRAWN	MAHALINGAM		DATE	01-03-2024


STRUCTURAL CONSULTANTS:


C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai-600 020.


C.KANNAN B.E., M.E(STRUCTURE)
DOOR NO:21, PLOT NO:257-W,
FLAT NO:2B, "UTOPIA APARTMENTS",
2nd FLOOR, 4th MAIN ROAD,
INDIRA NAGAR, CHENNAI-20.
MOBILE NO: 098412 49815.
E-MAIL:kannanids2007@gmail.com


FILE NAME : D/MAHALINGAM/2024/PUSHKAR-ASHOK NAGAR


























Notes: –

1. This drawing should be read along with architectural drawings.
2. Grade of R.C.C. items shall be M30 for column & M25 for all other R.C.C works
3. Y Denotes TOR40 Steel confirming to I.S. 1786 – 2008. Grade – Fe 500
4. Clear cover to the main steel
   50 for Footings , Raft Slabs & Raft Beams.
   40 for Columns.
   25 for Lintel & Beams.
   20 for Sunshade & Slab.
5. Lap length shall be 50 d (Max. dia) for all bars.
6. —— Bottom Reinforcement
7. ----- Top Reinforcement
8. Provide Continuous Chairs to keep the top Reinforcement in position
9. Provide Y 8 at 200 as Distribution steel for all top Reinforcement.
10. Spacer Bar to be Provided in Between Two Layers Of Reinforcement of Same Dia at Every 1000 C/ C.
11. Not more than 40% of Reinforcement shall be Lapped at any particular junction.
12. Cantilever props should not be released until the roof is concreted.
13. Foundation is designed for Stilt plus five upper floor only.
14. For Earthquake analysis Zone III is taken as per IS : 1893-2016 code.
15. Removal of formworks :
    i) For Slabs :
    a. Slabs spanning upto 4.5 m (15'-0") – 7 days
    b. Slabs spanning over 4.5 m (15'-0") – 14 days
    ii) For Beams and Arches :
    c. Beams and Arches spanning upto 6 m (20'-0") –14days
    d. Beams and Arches spanning over 6 m (20'-0") –21days

R.NO	DATE	DESCRIPTION

PROJECT

PROPOSED RESIDENTIAL BUILDING AT DOOR NO:E-1 TO E-6, BLOCK-E, 54TH STREET/56TH STREET, ASHOK NAGAR, CHENNAI-600083. COMPRISED IN OLD S.NO:220 PART, T.S.NO:2, BLOCK NO:72 OF KODAMBAKKAM, VILLAGE WITHIN THE LIMITS OF GRETER CHENNAI CORPORATION. OLD DIVISION:132, NEW DIVISION:135, ZONE:10.

TYPICAL FLOOR ROOF DETAIL

DESIGNED	KANNAN		SCALE	1 : 100
DRAWN	MAHALINGAM		DATE	01-03-2024

STRUCTURAL CONSULTANTS:

C. KANNAN, B.E., M.E, (Structure)
Structural Engineer,
CMDA Reg. No: SE/I/2024/2/0047
Door No: 21, 4th Main Road,
Indira Nagar, Chennai - 600 020.

C.KANNAN B.E., M.E(STRUCTURE)
DOOR NO:21, PLOT NO:257-W,
FLAT NO:2B, "UTOPIA APARTMENTS",
2nd FLOOR, 4th MAIN ROAD,
INDIRA NAGAR, CHENNAI-20.
MOBILE NO: 098412 49815.
E-MAIL:kannankds2007@gmail.com

FILE NAME : D/MAHALINGAM/2024/PUSHKAR-ASHOK NAGAR



our services doesn't just end there

Buying & Selling Services

Property Buying Assistance, Property Selling Support, Market Price Analysis, Owner Outreach and Negotiation.

Legal & Documentation Services

Certified EC, Patta, legal opinions, property verification, due diligence, litigation solutions, and legal heir certificates.

Property Development & Approvals

Building plan approvals, construction, layout and sub-division approvals, zone conversion, and occupancy certification.

NRI & Investment Services

Escrow Services, Rentals, Litigation Solutions, Property Valuation and Property Management

Compliance & Special Services

Demolition, Vaasthu checks, regularization of unauthorized buildings, and office space solutions.



empowering your real estate decisions with smart tools

Property Valuation & Cost Estimation

Guideline Value, Apartment Composite Value, Stamp Duty & Registration Fees Calculator, Building Value Calculator, Capital Gains Calculator, Area Unit Converter, Length Unit Converter

Ownership, Compliance & Legal Verification

Encumbrance Certificate (EC) Search, Find Your SRO, Temple Property Check, WAQF Property Check, View Patta/Chitta, View FMB, Patta Analyzer, EC Analyzer

Zoning & Land Use Analysis

Land Use Zone Finder, CRZ Zone Check, Aquifer Zone Check, CBA Check, EWS Check, Road Width Check, Proposed Road Widening Check, FSI Calculator

Property Documentation & Workflow Tools

Forms & Templates, Document Generator, Document Translation, Dictionary

Vastu & Property Management Tools

Home Vastu Shastra, Plot Vastu Shastra, Property Management

Verified RealEstate™

We're honored to be part of your real estate journey

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai, India

hello@verified.realestate
+91 9996 12 9996
www.verified.realestate