Verified RealEstate™

Your trusted partner for buying, selling, and managing property, ensuring hassle-free service with 100% transparency.

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai, India

hello@verified.realestate
+91 9996 12 9996

Official Property Record

Digitally Verified Record - Powered by Verified RealEstate™



Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

STRUCTURAL STABILITY CERTIFICATE AND DESIGN CALCULATIONS

Name of work : Plan showing the proposed residential building in survey no. 142/A / 1C1 at Kilaambakkam village, Chengalpet taluk, Kancheepuram district.

Preamble:

1.the usage of the building-Stilt floor + 5 upper floors.

2 The Super Structure is built on outer 200mm walls and inner 100mm walls.

3. Concrete grade for RCC members is M30 grade concrete.

4. The SBC of the soil is 15Ton/sq.m.

5. The structural design includes the Earth quake Criteria as per IS: 1893(part 1)-latest revision.

This is to certify that the Structural Design of the proposed construction of residential building at above said site has been DESIGNED on the basis of EARTHQUAKE RESISTANT DESIGN OF STRUCTURES IS 1893 (Part1): 2002 General Provisions & Buildings, with latest declaration of Seismic Zone III, Zone factor 0.16 and according to I.S. Loading standards I.S. – 875. All precautions have been taken as per the CONTENTS OF REPORT FOUNDATION ANALYSIS. This Report has recommendations for effect of Seismic Condition for this Soil.

ADDITIONAL CRITERIA

1. The structure is idealized as Special RC-Moment Resisting Frame (SMRF) and analyzed using software package (STAAD PRO) for both vertical and lateral loads.
2. The lateral load includes wind load and earthquake load, Seismic load of medium and moderate intensity of ZONE-III considered is for design and analysis purpose.
3. The Foundation is designed for critical un-Factored load combinations.
4. The Superstructure members are designed for actual flexure, shear and forces.
5. The structure is analyzed for specific loads (Dead and Live Loads) and for the load combinations given in relevant loads.
6. The design of the structure is **structurally sound and safe.**

Er. P. RAMAN, B.E (CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

2. DESIGN CALCULATIONS.

CALCULATION OF SEISMIC CO-EFFICIENT

Name of city	: Kilaambakkam
Type of Building	: Residential Building
Building Frame System	: Special RC-Moment resisting frame (SMRF)
Fundamental Natural Period (Ts)	: (0.09*h/(d^0.5))=0.41sec.
Soil conditions	: medium
Zone Factor (Refer Table:2) (Z)	: 0.16 (moderate)
Importance Factor (Refer Table:6) (I)	: 1
Response Reduction (Refer Table:7)	: 5.0
Average response acceleration Co-efficient (Sa/g)	: 2.5

EARTH QUAKE ANALYSIS:

Horizontal Seismic Co-efficient (Ah)	= (Z/2)(I / R)(Sa/g) = (0.16/2) (1/5.0) (2.5) = 0.04
Design value of Ah	= 0.04
Type of Foundation	: Strip Raft foundation

1. GENERAL LOADING CONDITIONS:

(a) Imposed loads on Roof	- 1.50kN/m^2
(b) Imposed loads on Hall, Kitchen. & Bed, Residential	- 2.00kN/m^2
(d) Dead weight of R.C.C	- 25kN/m^3
(e) Dead weight of Brick Work	- 20kN/m^3

Er. P. RAMAN, B.E.(CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

2. LOADING ON SLAB:

2.1 Loading on Roof slab:

Roof finished with lime concrete terracing	=(0.10)(20)	=2.000kN/m^2
S/W of slab 150mm thick	=(.150)(25)	=3.75kN/m^2
Dead load	=5.75kN/m^2	
Live load	=1.50kN/m^2	
Total load on Roof	= 7.25kN/m^2	

2.2 Loading on Floor slabs:

Floor finish	= 1.00kN/m^2
S/w of slab 150mm thick	= 3.75kN/m^2
Dead load	=4.75kN/m^2
Live load	=2.00kN/m^2
Total load on Roof	= 6.75kN/m^2

Er. P. RAMAN, B.E (CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**


E-mail: raman_str@yahoo.co.in

DESIGN CALCULATION

3 DESIGN:

3.1 COLUMN DESIGN

Grade of Concrete			M 30	
Characteristic Strength of Reinf.		N/mm^2	500	
Width of Column	b	mm	600	
Depth of Column	D	mm	300	
Unsupported Length of Column	l_x	mm	3000	
Unsupported Length of Column	l_y	mm	3000	
Clear Cover to Reinf.		mm	40	
Diameter of Bar		mm	25	
Load		T		
Moment	M_{xx}	T.m		
Moment	M_{zz}	T.m		
Factored Load	P_u	kN	2313.000	1
Factored Moment	M_{ux}	kN.m	46.000	1
Factored Moment	M_{uz}	kN.m	123.000	1
Effective Length of Column	l_{ex}	mm	3600	1.2
	l_{ez}	mm	3600	1.2
	l_{ex}/D		12	0
			<12- Short Column	
	l_{ey}/b		6	0
			<12- Short Column	
Additional Moment due to Slender	M_{ax}	kN.m	0	
Additional Moment due to Slender	M_{az}	kN.m	0	
Percentage of Reinf.	p		3	
Gross Area of Cross Section	A_g	mm^2	180000	
Ultimate Axial Load	P_{uz}	kN	4382.1	
d'/D (about x-x axis)			0.175	0.2



Er. P. RAMAN, B.E.(CIVIL), M.E (Struct), M.I.E., C.Engg.
Registered Structural Engineer Grade - I (SE)
CMDA Registration No. SE/GR - I/19/02/000
S.S Manians Apartments
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

d'/D (about y-y axis)			0.088	0.1
(Table 60)	k1		0.184	
	k2		0.028	
	P_{bx}	kN	1008.720	
	k1		0.207	
	k2		0.328	
	P_{bz}	kN	1294.920	
	k_x		0.613	
	k_y		0.670	
Minimum Eccentricity	e_x	mm	16	
	e_y	mm	26	
Moments due to min. eccentricity	M_{ex}	kN.m	37.01	< 46.000 kN.m
Moments due to min. eccentricity	M_{ez}	kN.m	60.14	< 123.000 kN.m
Total Moments for which the column is to be designed are				
	M_{ux}	kN.m	46.000	
	M_{uz}	kN.m	123.000	
The section is to be checked for biaxial bending				
	$P_u/f_{ck}bD$		0.428	
	p/f_{ck}		0.1	
Referring (d'/D is 0.2)	$M_u/f_{ck}bD^2$		0.11	
	M_{ux1}	kN.m	178.200	
Referring to (d'/D = 0.1)	$M_u/f_{ck}bD^2$		0.140	
	M_{uy1}	kN.m	453.600	
	M_{ux}/M_{ux1}		0.258	
	M_{uy}/M_{uy1}		0.271	
	P_u/P_{uz}		0.528	
		a	1	1.5467 < 1
Mux/Mux1 + Muy/Muy1			0.256	OK
Area of Reinforcement	As	mm^2	5400	
Minimum no of to be provided			6	
No of Bars to be provided	Nos.		12	
Provide 12 Nos of 25 Diameter				

Er. P. RAMAN, B.E.(Civil), M.E (Struct), M.I.E., C.Eng.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/CR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

3.2 FOUNDATION DESIGN

3.2.1 STRIP RAFT FOOTING DESIGN

3.2.1.1 RAFT BEAM – RB1:

Beam Data

width	700 mm
depth	700 mm
clear cover to main reinf.	50 mm
Slab Thickness	250 mm

d' = 71 mm *.= cc+ sdia + mdia/2*

eff depth = 630 mm *.= d - d'*

Material Grades

Concrete	30 MPa
Steel	500 MPa

	Span Moment	Support Moment
Mu/bd²	0.00	2.99
xumax	287	287
Mulim	1107	1107
Mulim/bd²	3.99	3.99

Span Moment	0 KN-m	
Support Moment	829 KN-m	829 KN-m
		0 KN-m

Span Reinforcement

Beam is designed as
Singly Reinforced Beam
Minimum % of Steel as per IS 456 clause 25.5 required

Area of Steel	Tension (Ast)	Compr (Asc)
Percentage	0.170 %	------
Area of Steel	749 sqmm	

Refer Table 2 SP 16 pg 48

829 KN-m

Tension Reinforcement

Type	Bar dia	Nos	Area of Steel
Layer 1	25 mm	8	3927 sqmm
Layer 2	20 mm	0	0 sqmm
Layer 3	20 mm	0	0 sqmm
		Total Steel Provided	3927 sqmm

4421 sqmm

0.891 %

Provided Steel OK

Er. P. RAMAN B.E (CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

Compression Reinforcement

Type	Bar dia	Nos	Area of Steel
Layer 1	16 mm	0	
Layer 2	20 mm	0	
Layer 3			
Total Steel Provided			#VALUE!

Support Reinforcement

Beam is designed as
Singly Reinforced Beam

Area of Steel	Tension (Ast)	Compr (Asc)	
Percentage	0.792 %	------	*Refer Table 2 SP 16 pg 48*
Area of Steel	3491 sqmm		

Tension Reinforcement

Type	Bar dia	Nos	Area of Steel
Layer 1	25 mm	8	3927 sqmm
Layer 2	20 mm	0	0 sqmm
Layer 3	12 mm		0 sqmm
Total Steel Provided			3927 sqmm
Provided Steel OK			0.891 %

1.78236278996357

-0.721181394981786

-0.622131789249019

4211 sqmm
3852 sqmm

Compression Reinforcement

Type	Bar dia	Nos	Area of Steel
Layer 1	20 mm	0	
Layer 2	25 mm	0	
Layer 3			
Total Steel Provided			#VALUE!

4893 sqmm

Shear Force (Vu)	820 KN		
ζv	1.802	*.=Vu / (b * d)*	
ζc	0.627	*Refer Table 61 SP 16 pg 179*	*or =(0.85*√(0.8*fck)*√(1+5β)-1)) / (6β)*
ζcmax	3.5	*Refer Table J SP 16 pg 175*	

Er. P. RAMAN, B.E.(CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE
CMDA Registration No: SE/GR - I/19/02/00
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

Type	Bar Dia	Nos	Area of Steel
Layer 1	25 mm	0	0 sqmm
Layer 2	25 mm	0	0 sqmm
Layer 3	20 mm	0	0 sqmm
			0 sqmm

0.000 %

Sectional Dimensions
OK
Shear Reinforcements
required

Steel	500 MPa
Type of stirrup	6 legged
Stirrup diameter	8 mm
Spacing	152 c/c

Not Safe

Vus/d 8.636 kN/cm 8.636

3.3 BEAM DESIGN

Beam Data

width	200 mm
depth	600 mm
clear cover to main reinf.	25 mm
Slab Thickness	125 mm

d' 43 mm .= cc+ sdia + mdia/2
eff depth 557 mm .= d - d'

Material Grades

Concrete	30 MPa
Steel	500 MPa

	Span Moment	Support Moment
Span Moment 121 KN-m	Mu/bd²	1.95	4.56
	xumax	254	254
	Mulim	248	248
Support Moment 283 KN-m / 283 KN-m	Mulim/bd²	3.99	3.99
0 KN-m			

Span Reinforcement
Beam is designed as Singly
Reinforced Beam

Er. P. RAMAN, B.E (CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

Area of Steel	Tension (Ast)	Compr (Asc)
Percentage	0.488 %	------
Area of Steel	544 sqmm	

Refer Table 2 SP 16 pg 48

404 KN-m

Tension Reinforcement

Type	Bar dia	Nos	Area of Steel
Layer 1	20 mm	3	942 sqmm
Layer 2	20 mm	3	942 sqmm
Layer 3	25 mm	0	0 sqmm
Total Steel Provided			1885 sqmm

2349 sqmm

1.692 %

Provided Steel OK

Compression Reinforcement

Type	Bar dia	Nos	Area of Steel
Layer 1	16 mm	2	
Layer 2	16 mm	0	
Layer 3			
Total Steel Provided			

#VALUE!

Support Reinforcement
Beam is designed as Doubly Reinforced Beam

Area of Steel	Tension (Ast)	Compr (Asc)
Percentage	1.274 %	0.155 %
Area of Steel	1419 sqmm	173 sqmm

Refer Table 45-56 SP 16 pg 81-92

Tension Reinforcement

Type	Bar dia	Nos	Area of Steel
Layer 1	20 mm	3	942 sqmm
Layer 2	20 mm	3	942 sqmm
Layer 3			0 sqmm
Total Steel Provided			1885 sqmm

3.38412135036603

-1.203850642586300

-0.785897531029734

1.692 %

Provided Steel OK

2139 sqmm

1780 sqmm

Er. P. RAMAN, B.E (CIVIL), M.E (Struct), C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

Compression Reinforcement

2821 sqmm

Type	Bar dia	Nos	Area of Steel
Layer 1	25 mm	0	0 sqmm
Layer 2			0 sqmm
Layer 3			0 sqmm
	Total Steel Provided		0 sqmm

0.000 %

Provided Steel Insufficient

Shear Force (Vu)	**182 KN**		
ζv	1.634	.=Vu / (b * d)	
ζc	0.796	*Refer Table 61 SP 16 pg 179*	*or =(0.85*√(0.8*fck)*√(1+5β)-1)) / (6β)*
ζcmax	3.5	*Refer Table J SP 16 pg 175*	

Type	Bar Dia	Nos	Area of Steel
Layer 1	25 mm	0	0 sqmm
Layer 2	25 mm	0	0 sqmm
Layer 3	20 mm	0	0 sqmm
			0 sqmm

0.000 %

Sectional Dimensions OK
Shear Reinforcements required

Steel	**500 MPa**	Vus/d	1.676 kN/cm	1.676
Type of stirrup	**2 legged**			
Stirrup diameter	**8 mm**			
Spacing	261 c/c	Safe		

Er. P. RAMAN, B.E.(CIVIL), M.E.(Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

3.4 SLAB DESIGN

Slab thickness	t	150 mm
Concrete	fck	30 MPa
Steel	fy	500 MPa

Sunken Depth	0 mm

Loading

Slab Load

Dead Load	DL	3.750 KN/m
Live Load	LL	2.000 KN/m
Finishes Load	WL	1.000 KN/m
Total Load	Ws	6.750 KN/m
Factored Load	Wsu	10 KN/m

Sunken Slab Load

Dead Load	DL	3.750 KN/m
Filler Load	FL	0 KN/m
Live Load	LL	3.0 KN/m
Finishes Load	WL	1.0 KN/m
Total Load	Wsk	7.75 KN/m
Factored Load	Wsku	12 KN/m

Slab Data

Slab Type	Regular
Load	10 KN/m
Longer Span (ly)	5.30 m
Shorter Span (lx)	3.30 m

ly/lx ratio	1.61
Slab type	+

Loading on edges		*one way*	*two way*
W_{longer}	**15 KN/m**	*.=w*lx/2*	*.=(w*lx/2) + (1-(1/3)*(lx/ly)^2)*
$W_{shorter}$	**11 KN/m**		*.=w*lx/3*

Moments		*one way*	*two way*
Mx	10 KN-m	*.=w*lx^2/ 8*	*.=αx * w*lx^2*
My	6 KN-m		*.=αy * w*lx^2*

Thickness Check	OK	*.=Mulim > Mux or Muy*
Deflection	14 mm	*.= 5*W*l^4/(384EI)*

Er. P. RAMAN, B.E (CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.

Er. P.RAMAN,B.E.,(CIVIL)M.E.,(Struct)
STRUCTURAL ENGINEER.
S.S Manian's Apartment,
5/13, Thambiah Road Extn.,
West mambalam,
Chennai- 600 033.

Phone: **044-43512027**

E-mail: raman_str@yahoo.co.in

Area of Steel	Astx	Asty
	178 sqmm	**180 sqmm**

Refer Chart 4 SP 16 pg 21
Refer Table 5-44 SP 16 pg 51-80

or


Spacing required in mm

8#		10#		12#		16#	
x	y	x	y	x	y	x	x
283 c/c	**279 c/c**	**442 c/c**	**436 c/c**	**637 c/c**	**628 c/c**	**#######**	**1117 c/c**



*.=ast of bar*1000/ast req*


Final Ast provided	x	y
	10# @ 100c/c	**10# @ 150c/c**


Er. P. RAMAN (B.E., (Civil), M.E., (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/008
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.




STRIP RAFT FOUNDATION LAYOUT

SL. NO	COLUMN MARK	RC WALL SHAPE AND SIZE	FLOORS
1.	RCW1		BELOW GROUND LVL. (M30)
2.	RCW1		GROUND AND 1st FLOOR LVL. (M30)


SL. NO	COLUMN MARK	RC WALL SHAPE AND SIZE	FLOORS
3.	RCW1		2nd floor to 5th FLOOR LVL. (M30)




TYPICAL TIES ARRANGEMENT IN COLUMN




C.S OF (RB) TYPICAL -NTS




SPLICE WITH UPPER BARS CRANKED INTO POSITION INSIDE LOWER BARS



ANCHORAGE DETAIL FOR REDUCTION IN SIZE OF COLUMN AT 1ST FLOOR LEVEL



C.S OF RB2



C.S OF RB1

SCHEDULE OF FOOTING & SCHEDULE OF COLUMNS (MIX:30)

TYPE	COLUMN SIZE	COLUMN REINFORCEMENT				
		GROUND FLOOR	1st & 2nd FLOOR	3rd & 4th FLOOR	5th FLOOR	STIRRUPS
C1	300X800	12–#25	12–#25	12–#20	8–#20+4#16(b)	#8Tor
C2	300X530	10–#25	10–#25	10–#25	8–#25+2#20(b)	#8Tor
C3	200X750	12–#25	12–#25	12–#25	12–#25	#8Tor
C4	300X530	12–#25	12–#25	12–#25	8–#25+4#20(b)	#8Tor

NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETRES.
2. THIS DRG SHALL BE READ IN CONJUNCTION WITH RELEVANT ARCHITECTURAL DRAWINGS
3. ALL DIMENSIONS SHALL BE CHECKED AND VERIFIED BEFORE EXECUTION OF WORKS.
4. CONCRETE MIX :–
   FOR COLUMNS : M30.
   (CEMENT CONTENT –360 KG/M3)
   * CONTRACTOR / CLIENT SHALL SEND US CUBE TEST RESULTS TO SUBSTANTIATE THE CONCRETE MIX GRADE.
   * IF READY MIXED CONCRETE IS BEING USED, CLIENT/CONTRACTOR SHALL CAST CONCRETE CUBES INDEPENDENTLY AT SITE AND SEND CUBE RESULTS THUS OBTAINED TO US.
5. MAXIMUM WATER CEMENT RATIO :
   FOR 1:1 1/2:3 – 0.45
6. REINFORCEMENT :
   TOR STEEL FOR #8MM & ABOVE CONFORMING TO IS 1786 (LATEST REVISION) Fe–500 GRADE
7. CLEAR CONCRETE COVER TO MAIN BARS :
   FOR COLUMNS : 40MM ,FOR RC WALL : 25MM
   FOR FOOTINGS&RAFT SLAB : 50MM, RAFT BEAM: 75MM
8. USE STONE AGGREGATES AND SAND CONFORMING TO IS 383 (LATEST REVISION)
   STONE AGGREGATES SIZE – 20MM AND DOWN GRADE
9. USE GOOD WATER FOR CONCRETE MIXING AND CURING CONFORMING TO IS 456 (LATEST REVISION)
10. USE ORDINARY PORTLAND CEMENT CONFORMING TO IS 8112 (LATEST REVISION) FOR 43 GRADE CEMENT & IS 12269 FOR 53 GRADE CEMENT.
11. FOUNDATION IS DESIGNED FOR STILT+5FLOOR
12. THE CENTERING AND SHUTTERING TO SUPPORT STRUCTURAL CONCRETE MUST BE SUFFICIENTLY STRONG AND RIGIDLY BRACED.HORIZONTAL TIES SHALL BE PROVIDED AT EVERY 1.5M HEIGHT.
13. THE STABILITY OF SUPPORTS AND STRENGTH OF THE CENTERING AND FORMWORK SHOULD BE ENSURED BY THE CONTRACTOR AND SITE ENGINEER BEFORE PLACING CONCRETE.
14. THE SAFE BEARING CAPACITY OF SOIL IS –15t/m2 AT 2.8M DEPTH.
15. USE ANTI CORROSIVE AGENT FOR ALL STEEL BEFORE CONCRETING.

SCALE	1:100	DESIGN BY	–
JOB NO	–	DRAWN BY	–
DRG NO	S–01	DATE	–

DRAWING TITLE:


FOUNDATION LAYOUT

PROJECT :


PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING IN SURVEY NO. 142/A / 1C1 AT KILAAMBAKKAM VILLAGE CHENGALPET TALUK KANCHEEPURAM DISTRICT.

STRUCTURAL CONSULTANT

Er. P. RAMAN, B.E (CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.




SLAB BEAM LAYOUT.



SLAB REINFORCEMENT DETAILS

SLAB	SLAB THICKNESS	SLAB TYPE	MAIN BAR	SECONDARY BAR
S1	125mm	TWO WAY	#8MM@ 100mm	#8MM@ 125mm
S2	125mm	TWO WAY	#8MM@ 100mm	#8MM@ 125mm
S3	125mm	TWO WAY	#8MM@ 125mm	#8MM@ 175mm
S4	125mm	TWO WAY	#8MM@ 125mm	#8MM@ 150mm
S5	125mm	ONE WAY	#8MM@ 100mm	#8MM@ 150mm
S6	125mm	ONE WAY	#8MM@ 100mm	#8MM@ 150mm



TYPICAL SLAB ROD BENDING DETAILS.

NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETRES.
2. THIS DRG SHALL BE READ IN CONJUNCTION WITH RELEVANT ARCHITECTURAL DRAWINGS
3. ALL DIMENSIONS SHALL BE CHECKED AND VERIFIED BEFORE EXECUTION OF WORKS.
4. CONCRETE MIX :-
   FOR COLUMNS : M30.
   (CEMENT CONTENT -360 KG/M3)
   - CONTRACTOR / CLIENT SHALL SEND US CUBE TEST RESULTS TO SUBSTANTIATE THE CONCRETE MIX GRADE.
   - IF READY MIXED CONCRETE IS BEING USED, CLIENT/CONTRACTOR SHALL CAST CONCRETE CUBES INDEPENDENTLY AT SITE AND SEND CUBE RESULTS THUS OBTAINED TO US.
5. MAXIMUM WATER CEMENT RATIO :
   FOR 1:1 1/2:3 - 0.45
6. REINFORCEMENT :
   TOR STEEL FOR #8MM & ABOVE CONFORMING TO IS 1786 (LATEST REVISION) Fe-500 GRADE
7. CLEAR CONCRETE COVER TO MAIN BARS :
   FOR COLUMNS : 40MM ,FOR BEAM : 25MM
   FOR ROOF SLAB : 20MM,
8. USE STONE AGGREGATES AND SAND CONFORMING TO IS 383 (LATEST REVISION)
   STONE AGGREGATES SIZE - 20MM AND DOWN GRADE
9. USE GOOD WATER FOR CONCRETE MIXING AND CURING CONFORMING TO IS 456 (LATEST REVISION)
10. USE ORDINARY PORTLAND CEMENT CONFORMING TO IS 8112 (LATEST REVISION) FOR 43 GRADE CEMENT & IS 12269 FOR 53 GRADE CEMENT.
11. THE CENTERING AND SHUTTERING TO SUPPORT STRUCTURAL CONCRETE MUST BE SUFFICIENTLY STRONG AND RIGIDLY BRACED.HORIZONTAL TIES SHALL BE PROVIDED AT EVERY 1.5M HEIGHT.
12. THE STABILITY OF SUPPORTS AND STRENGTH OF THE CENTERING AND FORMWORK SHOULD BE ENSURED BY THE CONTRACTOR AND SITE ENGINEER BEFORE PLACING CONCRETE.
13. USE ANTI CORROSIVE AGENT FOR ALL STEEL BEFORE CONCRETING.

SCALE	1:100	DESIGN BY	-
JOB NO	-	DRAWN BY	-
DRG NO	S--02	DATE	-

DRAWING TITLE:

SLAB BEAM LAYOUT.

PROJECT :

PLAN SHOWING THE PROPOSED RESIDENTIAL BUILDING IN SURVEY NO. 142/A / 1C1 AT KILAAMBAKKAM VILLAGE CHENGALPET TALUK KANCHEEPURAM DISTRICT.

STRUCTURAL CONSULTANT

Er. P. RAMAN, B.E (CIVIL), M.E (Struct), M.I.E., C.Engg.,
Registered Structural Engineer Grade - I (SE)
CMDA Registration No: SE/GR - I/19/02/006
S.S Manians Apartments,
No.5/13, Thambiah Road Extn.,
West Mambalam, Chennai-600 033.



our services doesn't just end there

Buying & Selling Services

Property Buying Assistance, Property Selling Support, Market Price Analysis, Owner Outreach and Negotiation.

Legal & Documentation Services

Certified EC, Patta, legal opinions, property verification, due diligence, litigation solutions, and legal heir certificates.

Property Development & Approvals

Building plan approvals, construction, layout and sub-division approvals, zone conversion, and occupancy certification.

NRI & Investment Services

Escrow Services, Rentals, Litigation Solutions, Property Valuation and Property Management

Compliance & Special Services

Demolition, Vaasthu checks, regularization of unauthorized buildings, and office space solutions.



empowering your real estate decisions with smart tools

Property Valuation & Cost Estimation

Guideline Value, Apartment Composite Value, Stamp Duty & Registration Fees Calculator, Building Value Calculator, Capital Gains Calculator, Area Unit Converter, Length Unit Converter

Ownership, Compliance & Legal Verification

Encumbrance Certificate (EC) Search, Find Your SRO, Temple Property Check, WAQF Property Check, View Patta/Chitta, View FMB, Patta Analyzer, EC Analyzer

Zoning & Land Use Analysis

Land Use Zone Finder, CRZ Zone Check, Aquifer Zone Check, CBA Check, EWS Check, Road Width Check, Proposed Road Widening Check, FSI Calculator

Property Documentation & Workflow Tools

Forms & Templates, Document Generator, Document Translation, Dictionary

Vastu & Property Management Tools

Home Vastu Shastra, Plot Vastu Shastra, Property Management

Verified RealEstate™

We're honored to be part of your real estate journey

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai, India

hello@verified.realestate
+91 9996 12 9996
www.verified.realestate