Verified RealEstate™

RE REGULATORY RECORD

RERA Document


The document as the regulator published it, reproduced in full behind this page.

Published for reference. The authority's own register is the operative record.

Verified RealEstate™
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India

hello@verified.realestate
+91 9996 12 9996
verified.realestate

DIGITALLY VERIFIED RECORD



PUZHAL PANCHAYAT UNION

LAYOUT OF HOUSE SITES IN S.Nos.17/1B1, 24, 25/1A & 25/2 OF VADAKARAI VILLAGE

SCALE : 1:800 (ALL MEASUREMENTS ARE IN METRE)

SITE EXTENT (AS PER DOCUMENT) : 5563 SQ.M

ROAD AREA : 1614 SQ.M

PUBLIC PURPOSE AREA (1%)

PP-1 HANDED OVER TO THE LOCAL BODY 0.5% AREA: 23.0 SQ.M

PP-2 HANDED OVER TO THE TANGEDCO 0.5% AREA : 25.0 SQ.M : 48 SQ.M

NO. OF PLOTS : 20 Nos

CONVENIENT SHOP : 2 Nos

NOTE:
1. SPLAY - 1.5M x 1.5M
2. MEASUREMENTS ARE INDICATED EXCLUDING SPLAY DIMENSIONS
3. ROAD AREA WERE HANDED OVER TO THE LOCAL BODY VIDE GIFT DEED DOCUMENT NO.15031/2024, DATED: 21.11.2024, @ SRO REDHILLS
PUBLIC PURPOSE-1
PUBLIC PURPOSE-2 RESERVED FOR TANGEDCO

உள்ளாட்சி மன்றப் படி

CONDITIONS

(I)THE APPLICANT SHOULD FOLLOW THE CONDITIONS MENTIONED BY THE CE, PWD/WRD, CHENNAI REGION, CHEPAUK, CHENNAI-5 IN LETTER NO.DB/T5(3)/F 6636 VADAGARAI VILLAGE / 9025 / 2023 / DATED.16.11.2023, OBTAINED FOR FILE NO. LAYOUT-1/0001/2024 APPROVED LAYOUT NO.PPD/LO No.96/2024, ARE TO BE COMPLIED BY THE APPLICANT BEFORE ISSUING OF THE LAYOUT APPROVAL BY THE COMPETENT AUTHORITY (LOCAL BODY)

1. The applicants' land should be filled with earth filling with proper compaction to the minimum level of (+)10.100m (i.e.,) 5.200m below the Redhills Tank at F.T.L as (+)15.300m. To protect the site from inundation during floods. The process of earth filling and compaction should be done in layers of not more than 0.30metre deep to achieve required degree of compaction for the depth from (+)1.460m to (+)1.580m depending upon the existing field levels. Also, the applicants should provide emergency pumping operation for the seepage water, if it is proposed to have basement floor and as well as dewatering arrangements during flood periods. The all round pavement level within the site should not be less than (+)10.100m and the regular habitation should not be below MFL.
2. The applicants should clearly demarcate boundary of their land before commencement of any developmental activities in the presence of Revenue, Local body and WRD authorities concerned without fail and should not encroach the Government land and the same should be maintained as it is in the Revenue records.
3. The permission granted to the applicants, should not be altered / modified / changed to any others. Based on the records submitted by the applicants, the permission is granted. If any documents seem to be fake / manipulated / fabricated, in future the above permission will be cancelled without any correspondence. Hence, the applicants are solely responsible of genuinety of the documents submitted.
4. The WRD officers should be allowed to inspect the site at any time, during execution and thereafter, if necessary. Advance intimation should be given to the WRD officers concerned before commencement of work.
5. The applicants should abide by the rules and regulation of the WRD from time to time. The applicants should also abide court of law of both State & Central Government from time to time.
6. WRD is giving opinion only in connection with the inundation aspect and does not deliver any rights to the applicants to encroach the WRD / Government Lands in SF.Nos.37, 38, 39-3 & 42/river. The NOC for this site from the WRD is purely issued on the basis of inundation point of view.
7. The applicant should not carry out any other cross masonry structures across the River / Eri / Channel / Pond without prior permission from WRD if any damages occurred to the Channel / Odai or any water bodies that belong to government, the same should be restored and rectified to its original condition at their own cost by the applicant.
8. The channel in S.F.No.16 on Northern side boundary along the stretch of applicants land should be completely desilted and resectioned by constructing retaining wall on either side of the channel as per the FMB at the applicants own cost. The bed level of the above channel should be ascertained and resorted before commencing the development activity in presence of the Executive Engineer. Moreover the width of entire field channel as per Revenue records (FMB) within the stretch of applicants land should be maintained properly without any change in measurement as per Revenue records at any cost.
9. The Government field channel stretch abutting the boundary in S.F.No.16 on Northern side should be marked as per FMB and monitored and maintained by the applicant at his own cost. The width of the channel should be maintained without encroachment as per Revenue records and the hydraulic parameters of the field channel should make necessary periodical arrangements for free flow of water through the existing channel to the downside area within the proposed layout site. Also the applicant should de-silt the channel periodically and remove the obstruction then and there without any hindrance for free flow of water at his own cost boundary along the proposed land.
10. The applicants should not object at any time for the maintenance work / improvements work of the odai to be carried out by WRD. The applicant should not dump the garbages/debris in the odai and avoid the sewage water into the channel, etc,. The applicant should give an undertaking in writing to the effect that the above proposal will not obstruct in case any maintenance/improvement/ development works as per Revenue records [FMB] are to be carried out by WRD in future periodically.

Technical Suggestions:

a. The applicants should prepare the layout proposal by considering the suitable internal storm water drainage network drain as micro drains and lateral drain of suitable size within the site as per site condition. The same should be connected to the local drain / channel, rainwater harvesting, roads with road side drain and sewage treatment plant and its disposal and garbages/ debris and other solid waste management as per norms in existence within the applicant's land according to existing rules in force and should get proper approval from competent authority without fail.

b. The sewage or any unhygienic drainage (Treated or Untreated) should not be let into drain /channel/course at any cost and the debris and other materials should not be dumped into the drain / surplus course obstructing free flow of water. The applicants should make drainage network at their own cost and the same is to be connected to natural storm water drainage /channel. There is [illegible] in existence and as per the rules in force of CMDA (as per the circular issued by the office of the Commissioner of Town & Country Planning, Chennai- 2 vide Roc. No. 4307/2010-BA2/Dated: 13.03.2010) during development and there should not be any construction activity in future also, the CMDA should issue completion certificate only after obtaining compliance certificate NOC from WRD.

c. The applicants should get clearance certificate for this site from the Revenue department to make sure that the site is not an encroached property from the water body as well as confirming this proposed site boundaries.

d. The sewage water from the applicant land vacant land should not let into the drain and for the disposal of the sewage water, feasible arrangements should be made for the same by the applicants, and as well as the construction materials/debris/garbages should not be dumped into the channel/river/tank at any cost.

At any cost, sewage / sullage should not be let in not be let into channel/river, and the garbages, debris and construction materials should not be dumped into the channel/river restricting the free flow of water.

The owner of the document received from the applicants in respect to the ownership is purely of applicant's responsibility and it is only for reference purpose to this department. The legal validity of this document should be verified by the Development / Revenue authorities. The specific remarks on inundation are purely issued on technical grounds in respect to the physical location of land.

Failing to comply with any of the above conditions, WRD reserves rights to withdraw the Technical opinion on inundation point of view to the above proposed site and in event, the applicants shall not be eligible for any compensation whatsoever and as well as legal entity.

(II) TNCDBR-2019, RULE NO: 47 (11) [illegible] **47 (11)**

THE COST OF LAYING IMPROVEMENTS TO THE SYSTEMS IN RESPECT OF ROAD, WATER SUPPLY, SEWERAGE, DRAINAGE OR ELECTRIC POWER SUPPLY THAT MAY BE REQUIRED AS ASSESSED BY THE CONCERNED AUTHORITY, NAMELY, THE LOCAL BODY AND TAMIL NADU ELECTRICITY BOARD, SHALL BE BORNE BY THE APPLICANT.

(III) LOCAL BODY SHOULD ENSURE, ENSURE COMPLIANCE OF ALL THE CONDITIONS STIPULATED BY PWD IN THEIR LETTER NO.DB / T5(3) /F. 6636 VADAKARAI VILLAGE / 9025 / 2023 / 16.11.2023 OBTAIN A LETTER FROM PWD CONFIRMING THE COMPLIANCE OF THE CONDITIONS BEFORE THE SANCTION AND RELEASE OF THE LAYOUT.

(IV)THE APPLICANT IS RESPONSIBLE, ONSIBLE FOR THE SHAPE,SIZE & DIMENSIONS OF THE SITE UNDER REFERENCE.

NECESSARY SPACE FOR BUILDING WILDING LINE TO BE LEFT AS PER THE RULE IN FORCE WHILE TAKING UP DEVELOPMENT IN EVERY PLOT.

LEGEND:
- SITE BOUNDARY
- ROADS GIFTED TO LOCAL BODY
- EXISTING ROAD
- PUBLIC PURPOSE - 1 GIFTED TO LOCAL BODY
- PUBLIC PURPOSE - 2 GIFTED TO LOCAL BODY (FOR TANGEDCO)
- CONVENIENT SHOP
- CHANNEL

AGE

For ARIHANT FOUNDATIONS

Partner

OWNER'S SIGNATURE

R.Nagalingam

LICENSED SURVEYOR

This Planning Permission issued under New Rule TNCDBR, 2019 is subject to final outcome of the W.P.(MD) No.8948 of 2019 and WMP (MD) Nos. 6912 & 6913 of 2019.

CONDITIONS :
THE LAYOUT APPROVED IS VALID SUBJECT TO OBTAINING SANCTION FROM THE LOCAL BODY CONCERNED

Planning Permit No. 15994 Dated: 02.12.2024

P.P.D / L.O No: 276/2024

APPROVED

VIDE LETTER No.: Layout-1/0181/2024

DATED

For Member Secretary
Chennai Metropolitan Development Authority
Chennai-600 008.

CMDA

THE LANDLENS SUITE

Eight ways to know a piece of land before you pay for it.

This report covers one part of the picture. These cover the rest, drawn from the same government records, for any property in Tamil Nadu.

LandLens One
Ask anything about a property and get an answer grounded in live government records, with the sources shown.
/landlens/one

Verify My Land
Every record check run on one property and returned as a single report.
/landlens/verify-my-land

Legal Opinion
An advocate's written opinion on the title, built on the records we pull for it.
/landlens

One Map
Every layer on one map: the parcel, its boundary, zoning, water bodies and what sits around it.
/landlens/one/map

PriceMap
What land actually changed hands for around this plot, taken from the registered deeds.
/landlens/pricemap

Build Scope
What you are allowed to build here: floor space, height, coverage and setbacks.
/landlens/build-scope

Property Tracker
Watch a property and hear about it when something new is registered against it.
/landlens/property-tracker

Deal Room
Run the transaction in one place: documents, stamping, signatures and the parties.
/landlens/deal-room

FREE TOOLS · NO ACCOUNT NEEDED

Twenty-four checks you can run yourself, at no cost.

Records and verification

The registers themselves, read for you.

- Encumbrance Certificate
- Patta and Chitta
- Field Measurement Sketch
- EC Analyzer
- Bank charge check
- Court case search
- Seller background check
- Approval check by survey

Value and duty

What it is worth and what it costs to register.

- Guideline value by street
- Guideline value by survey
- Stamp duty and registration fees
- Capital gains
- Floor space index
- Area unit converter

Zoning and land use

What the plan says can happen on this land.

- Land use zone finder
- CMDA land use check
- Coastal regulation zone
- Master plan check
- Water bodies finder
- Airport height clearance

Registers and directories

Who holds it, and which office keeps the record.

- Find your registering office
- Temple property check
- Waqf property check
- RERA register

Every free tool
/tools

Services we run for you
/services

The LandLens suite
/landlens/one

Verified RealEstate™

Every claim in this document traces back to a government record.

- Legal opinions, due diligence and title verification
- Building plan, layout and sub-division approvals
- Completion and occupancy certificates, regularisation
- Escrow, negotiation and NRI property management
- Land survey, soil testing, architecture and construction

Verified RealEstate
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India
hello@verified.realestate
+91 9996 12 9996

Prepared from the registers named on the page each finding sits on. Where a register could not be read, this document says so in its place rather than leaving the gap to be read as a clean result.