Verified RealEstate™

Your trusted partner for buying, selling, and managing property, ensuring hassle-free service with 100% transparency.

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai, India

hello@verified.realestate
+91 9996 12 9996

Official Property Record

Digitally Verified Record - Powered by Verified RealEstate™



Water Resources Department

From
Er.M.Janaki, M.E., F.I.E.,
Chief Engineer, WRD.,
Chennai Region,
Chepauk, Chennai - 5.
Email id: cecrwrdhdo@gmail.com

To
The Member Secretary,
Chennai Metropolitan Development Authority,
No.1, Gandhi Irwin Road,
Egmore, Chennai – 600 008.

Letter No.DB /T5(3)/ F.NOC Online 7117Goparasanallur Village/2024/ Dated.09.09.2024.

Sir,

Sub: CMDA – Area Plan Unit – NHRB (Central) – Planning Permission for proposed Construction of Group Housing Development consisting 5 Blocks: Block A – Stilt floor + 5 floors (Height – 18.30m) Residential Building with 120 dwelling units; Block B – Stilt floor + 5 floors (Height – 18.30 m) Residential Building with 120 dwelling units; Block C – Stilt floor + 5 floors (Height – 18.30m) Residential Building with 61 dwelling units; Block D – Stilt floor part / Ground floor part + 5 floors (Height – 18.30m) Residential Building with 72 dwelling units; Totally 373 dwelling units with swimming pool; Block E – Ground Floor + 5 floors (Height – 18.30m) Amenities Block with (Shop, Gym, SPA Room, Music Room, Games Room, Tuition Hall, Business Centre & Nursery) (Affordable Housing) at Goparasanallur Main Road, Goparasanallur, Chennai – 600077, comprised in Survey No.23/1A, 23/1B, 48/1B2, 49/1A, 49/1B, 49/1C2, 49/1D, 50/1A1B, 52/1B & 52/2A2 of Goparasanallur Village in Poonamallee Taluk of Thiruvallur District within the limits of Poonamallee Panchayat Union - Specific Remarks along with NOC on inundation point of view– issued – regarding.

Ref: 1.The Member Secretary (CMDA), Chennai-8 online Dated:06.05.2024

******

With reference to the 1st letter cited above, after careful consideration the technical opinion along with NOC on inundation point of view of this department is hereby accorded for proposed Construction of Group Housing Development consisting 5 Blocks: Block A – Stilt floor + 5 floors (Height – 18.30m) Residential Building with 120 dwelling units; Block B – Stilt floor + 5 floors (Height – 18.30 m) Residential Building with 120 dwelling units; Block C – Stilt floor + 5 floors (Height – 18.30m) Residential Building with 61 dwelling units; Block D – Stilt floor part / Ground floor part + 5 floors (Height – 18.30m) Residential Building with 72 dwelling units; Totally 373 dwelling units with swimming pool; Block E – Ground Floor + 5 floors (Height – 18.30m) Amenities Block with (Shop, Gym, SPA Room, Music Room, Games Room, Tuition Hall, Business Centre & Nursery) (Affordable Housing) at Goparasanallur Main Road, Goparasanallur, Chennai – 600077, comprised in Survey No.23/1A, 23/1B, 48/1B2, 49/1A, 49/1B, 49/1C2, 49/1D, 50/1A1B, 52/1B &

9/9/24

52/2A2 of Goparasanallur Village in Poonamallee Taluk of Thiruvallur District within the limits of Poonamallee Panchayat Union, in favour of M/s.LML Homes LLP.

The proposed site was inspected and ascertained that, the Ullur Thangal (Thangal Eri) in S.F.No.55 is located abutting the applicant's site on Western side along with a Thangal Bed (Eri Ulvoy) in S.F.No.56 on the same side, but not abutting the site. Further, the Government Channel in S.F.No.47 runs partially abutting the applicant's site in S.F.No.23/1A & 23/1B on Southern side. This Channel originates from Thangal Eri bearing S.F.No.55 of Goparasanallur Village, which runs from East – West direction. The channel was once used for Irrigation purpose and at present the channel is silted up condition since the above lands are converted to residential areas due to urbanisation and there are no cultivation activities in and around the proposed site. In addition to this, the Goparasanallur Main Road traverses on Northern side abutting the applicant's site in S.F.No.52/2A2, which in turn connects the Poonammallee High Road on Western side of the site.

In this regard, it was observed that a Plan marked channel or Bye-mass channel or Patta channel is found within the applicant's site in S.F.No.23/1A & 23/1B. Hence, the Applicant has to realign and form necessary suitable storm water drainage network (internally) within the site, so that the Ultimate disposal of storm water discharge into the nearby Government Channels which is running on South during rainy season in order avoid inundation.

During the site inspection, it was observed that, the Coovum River runs on Northern side, which about a distance of 1.6 Km from the applicant's site. The entire site was surrounded by Residential layouts along with few Commercial sites and Vacant lands on East and South direction. As per Revenue records, these lands are classified as "Dry & Wet" lands.

In order to ascertain the gravity of inundation of the said lands, the field levels were taken with reference to the Temporary Bench Mark from Known Datum of Poonamallee High Road level at (+) 20.585 m. As a safety measure, the proposed site must be analyzed with respect to the flood levels experienced during previous floods. The Observed Maximum Flood Level near the site is (+) 19.580 m. Further, the Goparasanallur Main Road Top level is (+) 20.110 m, which is on Northern side of the Applicant's land. To protect the site safe against any inundation in the near future, the site must be raised to a minimum level of 0.60m above the maximum flood level (or) nearest main road level whichever is higher, hence the site must be raised to a minimum level of 0.60m from road level. In order to protect the site

9/9/24

against inundation the site field level must be raised to minimum a level of (+) 20.110 + 0.600 = (+) 20.710 m (ie.,0.125m above the Poonamallee High Road level which is (+) 20.585 m). The field levels were taken at the proposed site and furnished for reference as below:

Sl. No.	Field Survey Number	Existing Field Level in m	Required height of filling with respect to the 2015 flood level (+)20.110 m + 0.60m = (+)20.710 m.	
			Required Level in m	Height Filling in m
1.	23/1A	(+)19.600	(+)20.710	1.110
2.	23/1B	(+)19.530		1.180
3.	48/1B2	(+)19.780		0.930
4.	49/1A	(+)19.760		0.950
5.	49/1B	(+)19.980		0.730
6.	49/1C2	(+)19.360		1.350
7.	49/1D	(+)19.820		0.890
8.	50/1A1B	(+)19.900		0.810
9.	52/1B	(+)19.920		0.790
10.	52/2A2	(+)19.950		0.760

Also the proposed land is to be raised (+)0.730 m to (+)1.350 m with hard earth with proper consolidation to avoid inundation problem during rainy season from the above existing field levels, the required filling varies from (+)0.730 m to (+)1.350 m to avoid inundation. Since, the existing field level is below MFL. The regular habitation should not be below MFL since the existing ground levels are below MFL.

Based on the available Revenue records and as much as considering the prevailing site conditions, necessary technical opinion along with NOC on inundation point of view, of this department for the Planning Permission for the proposed Construction of Group Housing Development consisting 5 Blocks: Block A – Stilt floor + 5 floors (Height – 18.30m) Residential Building with 120 dwelling units; Block B – Stilt floor + 5 floors (Height – 18.30 m) Residential Building with 120 dwelling units; Block C – Stilt floor + 5 floors (Height – 18.30m) Residential Building with 61 dwelling units; Block D – Stilt floor part / Ground floor part + 5 floors (Height – 18.30m) Residential Building with 72 dwelling units; Totally 373 dwelling units with swimming pool; Block E – Ground Floor + 5 floors (Height – 18.30m) Amenities Block with (Shop, Gym, SPA Room, Music Room, Games Room, Tuition Hall, Business Centre & Nursery) (Affordable Housing) at Goparasanallur Main Road, Goparasanallur, Chennai – 600056, comprised in Survey No.23/1A, 23/1B, 48/1B2, 49/1A, 49/1B, 49/1C2, 49/1D, 50/1A1B, 52/1B & 52/2A2 of S-49, Nombal Main

9/9/24

Road, Goparasanallur Village in Poonamallee Taluk of Thiruvallur District within the limits of Poonamallee Panchayat Union, Chennai - 77 in favour of M/s.LML Homes LLP is hereby issued subject to the following conditions and technical suggestions, besides any other mandatory clearance of statutory permission from any other organization or department if necessary, for the consideration of Planning permission by Chennai Metropolitan Development Authority.

CONDITIONS:

1. The applicant's land should be filled with earth with proper compaction to the level of (+)20.710 m to protect the site from inundation during floods. The process of earth filling and compaction should be done in layers of not more than 0.30m depth to achieve the required degree of compaction for a depth from (+)0.730 m to (+)1.350 m depending upon the existing field levels and the existing applicant land should be raised to a level of (+)20.710 m (ie.,0.125m above the Poonamallee High Road level which is (+)20.585 m). Also, the applicant should provide emergency pumping operation for the seepage water, if it is proposed to have basement floor as well as dewatering arrangements during flood periods. The applicant is suggested not to have regular habitation below MFL. The all round pavement level within the site should not be less than (+) 20.710 m and the regular habitation should not be below MFL.

2. The applicant should do proper soil test, and suitable foundation should be selected depending upon the soil condition and the structural design should be obtained from the approved and qualified Structural Engineer.

3. The WRD., will not be held responsible for the Structural Stability, safety and soundness of the building proposed by the applicant and WRD specifically recommend only for inundation point of view. The applicant is solely responsible for the structural safety and stability of the proposed building and at any cost, WRD will not be held responsible for design and drawing adopted for proposed construction.

4. The applicant should clearly demarcate the boundary of their land especially on Western and Southern side before the commencement of any developmental activities in presence of Revenue authorities and WRD and local body authorities concerned without fail and should not encroach the Government land and the same should be maintained as it is in the Revenue records.

5. The permission granted to the applicant, should not be altered/modified/ changed to any others. Based on the Revenue records submitted by the applicant, the permission is granted. If any documents seem to be fake / manipulated /

9/9/24

fabricated, in future the above permission will be cancelled without any correspondence. Hence, the applicant is solely responsible of genuinity of the documents submitted. If there is any discrepancy or any other encroachments activities, the applicant is held responsible in the future.

6. The WRD officers should be allowed to inspect the site at any time, during execution and thereafter, if necessary. Advance intimation should be given to the WRD officers concerned before commencement of work.

7. The applicant should abide by the rules and regulation of the WRD from time to time. The applicant should also abide court of law of both State & Central Government from time to time.

8. WRD is giving opinion only in connection with the inundation aspect and does not deliver any rights to the applicant to encroach the Government Lands. The NOC for this site issued from WRD is purely issued on the basis of inundation point of view.

9. The applicant should not object at any time for the maintenance works / improvement works of the channels which are proposed to be carried out by WRD. The applicant should give an undertaking in writing to the effect that the above proposal will not obstruct in case any maintenance / improvement / development works as per Revenue records [FMB], which are proposed to be carried out by WRD in future periodically.

10. The Government channel in S.F.No.47 abutting the applicant's land on South, should be completely desilted and resectioned by constructing retaining wall on either side as well as bed lining concrete of the channel as per the FMB at the applicant's own cost. The bed level of the above channel should be ascertained and restored before commencing the development activity in the presence of the concerned WRD Executive Engineer. Moreover the width of entire field channel as per revenue records (FMB) along & within the stretch of applicants land should be maintained properly without any change and encroachment at any cost.

11. The Government field channel in S.No.47 stretch abutting the applicant boundary in S.F.No.23/1A & 23/1B should be marked as per FMB and monitored and maintained by the applicant at their own cost. The width of the channel should be maintained without encroachment as per revenue records and the hydraulic parameters of the field channel should be maintained. The applicant should make necessary periodical arrangements for free flow of water through the existing channel to the downside area within the proposed layout site. Also the applicant

9/9/24

should de-silt the channel periodically and remove the obstruction then and there without any hindrance for free flow of water at their own cost within the proposed land, after the completion of project.

Technical Suggestion:

a. The applicant should prepare the layout proposal by considering the suitable internal storm water drainage network as micro drain of suitable sizes within the site as per site condition. The same should be connected to the local drain/channel, rainwater harvesting and sewerage treatment and its disposal and garbages/debris and other solid waste management as per norms in existence within the applicant's land according to existing rules in force and should get proper approval from competent authority without fail.

The sewage or any unhygienic drainage (Treated or Untreated) should not be let into drain / channel / course at any cost and the debris and other materials should not be dumped into the drain / surplus course obstructing free flow of water. The applicants should make drainage network, at their own cost and the same is to be connected to natural storm water drainage / channel. There should not be any hindrance to the free flow of internal drain to downstream.

b. The necessary setback distance should be provided with in the site according to the site condition as per the norms in existence and as per the rules in force of CMDA (circular issued by the office of the Commissioner of Town & Country Planning, Chennai – 2 vide Roc.No.4367 / 2019-BA2 / 13.03.2019) during development and there should not be any construction activities in further also. The CMDA should issue completion certificate only after obtaining compliance certificate NOC from WRD.

c. The applicant for this land should get a clearance certificate from the Revenue department to make sure that the site is not an encroached property of the water body as well as confirming this site boundary. The applicant lands are seemed to be ryotwari land which would be classified as **"Dry & Wet"** lands. Hence, these lands are to be converted into other zone from the agricultural zone by the competent authority.

d. The sewage water from the applicants' land should not let into the drains and for the disposal of the sewage water and suitable arrangements should be made for the same by the applicant and as well as the construction materials/debris/garbages should not be dumped into the channel / river at any cost.

9/9/24

At any cost, sewage/sullage should not be let into channel, and the garbages, debris and construction materials should not be dumped into the channel/river restricting the free flow of water.

The owner of the document received from the applicant in respect to the ownership is purely of applicant's responsibility and it is only for reference purpose to this department. The legal validity of this document should be verified by the Development / Revenue authorities. The specific remarks on inundation are purely issued on technical grounds in respect to the physical location of land.

Failing to comply with any of the above conditions, WRD reserves rights to withdraw the Technical opinion on inundation point of view to the above proposed site and in event, the applicant shall not be eligible for any compensation whatsoever and as well as legal entity.

9/9/24

for Chief Engineer, WRD.,
Chennai Region, Chennai-5.

9/9/24



our services doesn't just end there

Buying & Selling Services

Property Buying Assistance, Property Selling Support, Market Price Analysis, Owner Outreach and Negotiation.

Legal & Documentation Services

Certified EC, Patta, legal opinions, property verification, due diligence, litigation solutions, and legal heir certificates.

Property Development & Approvals

Building plan approvals, construction, layout and sub-division approvals, zone conversion, and occupancy certification.

NRI & Investment Services

Escrow Services, Rentals, Litigation Solutions, Property Valuation and Property Management

Compliance & Special Services

Demolition, Vaasthu checks, regularization of unauthorized buildings, and office space solutions.



empowering your real estate decisions with smart tools

Property Valuation & Cost Estimation

Guideline Value, Apartment Composite Value, Stamp Duty & Registration Fees Calculator, Building Value Calculator, Capital Gains Calculator, Area Unit Converter, Length Unit Converter

Ownership, Compliance & Legal Verification

Encumbrance Certificate (EC) Search, Find Your SRO, Temple Property Check, WAQF Property Check, View Patta/Chitta, View FMB, Patta Analyzer, EC Analyzer

Zoning & Land Use Analysis

Land Use Zone Finder, CRZ Zone Check, Aquifer Zone Check, CBA Check, EWS Check, Road Width Check, Proposed Road Widening Check, FSI Calculator

Property Documentation & Workflow Tools

Forms & Templates, Document Generator, Document Translation, Dictionary

Vastu & Property Management Tools

Home Vastu Shastra, Plot Vastu Shastra, Property Management

Verified RealEstate™

We're honored to be part of your real estate journey

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai, India

hello@verified.realestate
+91 9996 12 9996
www.verified.realestate