Verified RealEstate™

RE REGULATORY RECORD

RERA Document

The document as the regulator published it, reproduced in full behind this page.

Published for reference. The authority's own register is the operative record.

Verified RealEstate™
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India

hello@verified.realestate
+91 9996 12 9996
verified.realestate

DIGITALLY VERIFIED RECORD

TAMIL NADU FIRE AND RESCUE SERVICES DEPARTMENT

From
Thiru. Abhash Kumar, I.P.S.,
DGP / Director,
Tamil Nadu Fire and Rescue Services,
No.17, Rukmani Lakshmipathi Salai,
Egmore, Chennai – 600 008.

To
The Member Secretary,
Chennai Metropolitan Development Authority,
No.1, Gandhi Irwin Road,
Egmore, Chennai – 600 008.

R.Dis.No.16685/C1/2024 Dated.11.11.2024

PP NOC No. 199 /2024

Sir,

Sub : Tamil Nadu Fire and Rescue Services – Directorate – High Rise Building – Issue of Planning Permission NOC requested – Inspection at M/s. Escapade Services LLP, Plot No.29, Thiru-Vi-Ka Industrial Estate, Guindy, Chennai - 600 032 comprised Town Survey Nos.14/29, Block No.2, Situated at Alandur Village, Guindy Taluk, Chennai District - Reg.

Ref : 1) Online application token no.228068 dated:18.10.2024.
2) The Joint Director, Northern Region, Report Rc.No.5049/C/2024, Dated:28.10.2024.

****

Kindly refer to the letter cited above. The MSB inspection committee of the northern region has inspected the site of M/s. Escapade Services LLP, Plot No.29, Thiru-Vi-Ka Industrial Estate, Guindy, Chennai - 600 032 comprised Town Survey Nos.14/29, Block No.2, Situated at Alandur Village, Guindy Taluk, Chennai District for which the PP NOC has been requested. The committee has made certain observations with regard to fire and life safety, which are reproduced below:-

Observation:

It is a planning permission for the proposed construction of IT/ITES building consisting of Block A1 & Block A2. Block A1 consisting of Basement Floor + Stilt Floor + 7 Floors with the height of 30 meters (IT/ITES Building), Block A2 (Utility Building) consisting of Ground Floor with the height of 3.35 meters. The proposal has side setback of 7 meters all around the building. The plot area is 2347square meters and the total floor area is 8613.65square

meters. The proposal is classified as Group E Business Building, Sub-Division E-3 Computer Installations (IT/ITES) as per the National Building Code of India Part IV Fire and Life Safety-2016.

The following fire & life safety measures should be provided in the proposed building before the issue of compliance certificate as listed below:

1. There should be a wet-riser along with hose reel assembly per thousand square meters area covering all floor areas with landing valves along with delivery hoses. The raiser should be fully charged with adequate pressure at all times & should have both automatic and manual operation. To feed the wet-riser and sprinkler system an underground static water tank of minimum capacity 100000 liters should be provided with refilling facilities for per set of pumps. A terrace level tank of capacity 10000 liters also should be provided respective tower terrace. To charge the wet riser system and the sprinkler system one set of pumps contains one electrical pumps of capacity 2280 LPM for hydrants & sprinkler, an equal capacity of a diesel pump and one electrical pumps of each capacity of 180 LPM as a jockey pump should be provided near the underground water tank. The pumps should be capable of developing pressure of 3.5 kg/cm^2 at terrace level hydrant point.
2. Yard hydrant should be provided at all around the building every 30 meters.
3. Fire service inlets fitted with NRV at ground level should be provided.
4. Manually operated electric fire alarm system including talk back system to be provided at all floors.
5. Public address system should be provided connecting all the floors.
6. Automatic sprinkler system should be provided at all floors including basement and stilt floor.
7. Automatic detector system should be provided at all floors.
8. Alternative & independent power systems should be provided to fire pumps, emergency lighting system and fire lift.
9. BMS should be provided and automatic detection should be integrated to the BMS system and be manned 24X7.
10. Fire exit - internal staircases and external staircase:

The route to the external stairs shall be free of obstructions at all times.

The external stairs shall be constructed of non-combustible materials and any doorway leading to it shall have the required fire resistance.
No external staircase, used as a fire escape, shall be inclined at an angle greater than 45°from the horizontal.

Fire lifts: At least one lift should be designated as fire lift. Fire lifts shall be provided with a minimum capacity for 8 passengers and fully automated with emergency switch on ground level. In general, buildings 15m in height or above shall be provided with fire lifts.

In case of fire, only fireman shall operate the fire lifts. In normal course, it may be used by other persons.

Each fire lift shall be equipped with suitable inter-communications equipment for communicating with the control room on the ground floor of the buildings.

The number and location of fire lifts in a building shall be decided after taking into consideration various factors like building population, floor area, compartmentation, etc.,

11. The ramp to basement is provided within the building line. However, they should not provide any obstruction like transformer yard, generator, landscape, LPG bank etc., in the setback area, so as to facilitate the easy movement and operation of an aerial ladder platform vehicle during emergency. The setback area slop gradient should not be elevated from the ground level. The entry, movement and exit of the setback should have no slope and should be hard paved and support the operation of the aerial ladder platform.
12. The first aid firefighting equipment's should be provided at all floors in accordance with the IS 2190: 2010 requirements.

13. **Vehicular access within the site** – Internal vehicular access way including passage if any within the site shall have a clear width of 7.2m.

14. The basement shall have the following requirements:

- I) Design criteria:

  Ramps with very steep slopes are not allowed and gradient of 1 in 8 or more alone is permissible. Ramps should not be constructed affecting the open space adjacent to the building. It should meet the following criteria; access, ventilation, firefighting and escape provisions. Brightly lit, colour coded sections are must to identify the different sections of the basements.

- II) Flooding in basements:

  Basement shall be constructed in such a way that there should not be any water logging EB room / generator/ etc., shall not be installed in the basement.

  a) Every basement shall be in every part at least 2.4m in height from the floor to the underside of the roof slab or ceiling.

  b) Adequate ventilation shall be provided for the same as required by the particular occupancy according to byelaws. Any deficiency may be met by providing adequate mechanical ventilation in the form of blowers, exhaust fans, air-conditioning systems, etc.,

  c) The minimum height of the ceiling of any basement shall be 0.9m and the maximum, 1.2m above the average surrounding ground level;

  d) Adequate arrangements shall be made such that surface drainage does not enter the basement;

  e) The walls and floors of the basement shall be watertight and be so designed that the effects of the surrounding soil and moisture, if any are taken into account in design and adequate damp proofing treatment is given; and

  f) The access to the basement shall be separate from the main and alternative staircase supply from the licensee's service and alternative supply cables. The door/doors provided for the

g) Service room shall have fire resistance of not less than two hours.

15. Basement:

- Basements shall be separately ventilated. Vents with cross-sectional area (aggregate) not less than 2.5 percent of the floor area spread evenly round the perimeter of the basement shall be provided in the form of grills, or breakable stall board lights or pavement lights or by way of shafts.

  Alternatively, a system of mechanical ventilation system integrated with CO sensormay be provided with following requirements.

  a) Mechanical ventilation system shall be designed to permit 12 air changes per hour in case of fire or distress call. However, for normal operation, air changes schedule shall be as given in part 8 'Building Services, Section 3 Air conditioning. Heating and Mechanical Ventilation' of the Code.

  b) In multi-level basements, independent air intake and smoke exhaust shafts (masonry or reinforced concrete) for respective basement level and compartments therein shall be planned with its make-up air and exhaust air fans located on the respective level and in the respective compartment. Alternatively, in multi-level basements, common intake masonry (or reinforced cements concrete) shaft may serve respective compartments aligned at all basement levels. Similarly, common smoke exhaust / outlet masonry (or reinforced cement concrete) shafts may also be planned to serve such compartments at all basement levels. All supply air fans on respective levels shall be installed in fire resisting level shall be installed in fire resisting room of 120 min. Exhaust fans at the respective level shall be provided with back draft damper connection to the common smoke exhaust shafts ensuring complete isolation and compartmentation of floor isolation to eliminate spread of fire and smoke to the other compartments / floors.

  c) Due consideration shall be taken for ensuring proper drainage of such shafts to avoid insanitation condition. Inlets and extracts may

be terminated at ground level with stall board or pavement lights as before. Stall board and pavements lights should be in positions easily accessible to the fire brigade and clearly marked 'AIR INLET' or 'SMOKE OUTLET' with an indication or area served at or near the opening.

d) Smoke from any fire in the basement shall not obstruct any exit serving the ground and upper floor of the building.

e) The smoke exhaust fans in the mechanical ventilation system shall be fire rated, that is 250^0 C for 120 min.

f) The smoke ventilation of the basement car parking areas shall be through provision of supply and exhaust air ducts duly installed with its support and connected to supply air and exhaust fans. Alternatively, a system of impulse fans (jet fans) may be used for meeting the requirement of smoke ventilation complying with the following.

- Structural aspects of beams and other down stands / services shall be taken care of in the planning and provision of the jet fans.
- Fans shall be fire fated, that is 250^0 C for 120 min.
- Fans shall be adequately supported to enable operations for the duration as above.
- Power supply panels for the fans shall be located in fire safe zone to ensure continuity of power supply.
- Power supply cabling shall meet circuit integrity requirements in accordance with accepted standard [4(13)].
- Supply air shall be not be less than 5 m from any exhaust discharge openings.

- The staircase of basements shall be of enclosed type having fire resistance of not less than 2 h and shall be situated at the periphery of the basement to be entered at ground level only from the open air and in such positions that smoke from any fire in the basement shall not obstruct any exit serving the ground and upper stores of the building

and shall communicate with basement through a lobby provided with fire resisting self-closing doors of 1 h resistance.

- All floors shall be compartmented with area of each compartment not exceeding 3000 m^2. Compartmentation shall be achieved by means of fire barrier wall of 2h rating or water curtain nozzle (K-23). In case of water curtain, existing water storage shall be supplemented by water demand for water curtain nozzles for 60 min considering the largest size of compartment. The water supply for the water curtain nozzles shall be through independent electric pump of adequate capacity (flow and head) with piping / riser for the water supply to the nozzles. Separate pump to be provided for water curtain.

16. **Fire fighting pump house**

As per clause 5.1.2.2 of the National Building Code of India part IV fire and life safety 2016,

a) Pump room provided at basement floor.
b) It is preferable to install the pump house to provide positive suction. Pump house shall be situated so as to be directly accessible from the surrounding ground level.
c) Pump house shall be separated by fire walls all around and doors shall be protected by fire doors (120 min rating).
d) Pump house shall be well ventilated and due care shall be taken to avoid water stagnation.
e) No other utility equipment shall be installed inside the fire pump room.
f) Insertions like flexible couplings, bellows, etc., in the suction and delivery piping shall be suitably planned and installed.
g) Installation of negative suction arrangement and submersible pumps shall not be allowed.
h) Pump house shall be sufficiently large to accommodate all pumps and their accessories like PRVs, installation control valves, valves, diesel tank and electrical panel.
i) Battery of diesel engine operated fire pump shall have separate charger from emergency power supply circuit.

j) Exhaust pipe of diesel engine shall be insulated as per best engineering practice and taken to a safe location at ground level, considering the back pressure.

k) Fire pumps shall be provided with soft starter or variable frequency drive starter.

17. Glass of facade used in external walls shall comply with the following:
    a. For fully sprinklered buildings having fire separation of 9 m or more, tempered glass in a non-combustible assembly with ability to hold the glass in place, shall be provided. It shall be ensured that sprinklers are located within 600 mm of the façade glass providing full coverage to the glass.
    b. All gaps between floor slabs and façade assembly shall be sealed at all levels by approved fire resistance sealant material of equal fire rating as that of floor slab to prevent fire and smoke propagation from one floor to another.
    c. Facade glass at each floor shall have means to open at least 10 percent of the total facade area to exhaust smoke during emergencies. Such openings, with sill level at 1.2 m, shall be in the form of openable panels of size not less than 1500 mm x 1000 mm opening outwards.

18. Illuminated exit signage's should be provided with alternative source of power supply or battery back – up with "GLOW TYPE".
19. Service ducts and shafts: As per clause 3.4.5.4 of the National Building Code of India part IV fire and life safety 2016.
20. Fire lift, electrical installation and wiring, AC duct & other service ducts should meet the requirements of NBC of India, Part 8, 2016.
21. The width and height of any arch or gate, if any, should have the clearance of not less than 7 m respectively.
22. The compulsory open space as per DCR set back area all around the building should be designed to with stand a weight of 64 tons at any point of operation for the use of hydraulic platform vehicle. In any case, no ramp,

landscape garden and swimming pool shall be allowed in the setback are. The entire setback area earmarked shall be hard paved or provided with reinforced concrete so as to withstand the weight of the aerial ladder platform.

23. The service ducts such as power cables, communication cables, A/C ducts etc., should be protected with proper fire sealing/fire dampers.
24. The cable gallery should be routed through fire resistant duct or fire protected tray. Suitable detectors shall be provided along the lines of the cable gallery.
25. As per section 3.2 of BIS 12459, 1988 – code of practice for fire safety in cable regularization, 1m transparent fire retardant coatings shall be applied to all cables at termination points in electrical panels and all cables inside the distribution boxes.
26. Fire resistant and low smoke emission cable should be used.
27. Assembly points should be designated at the ground floor as per the requirements of fire and life safety measures.
28. Dos and don'ts laminated hanging pads should be available in all floors in prominent places.
29. Evacuation route plan should be displayed in each floor at prominent places.
30. If the construction is done with prefabricated materials, sufficient natural vent / mechanized ventilation system should be provided.
31. A trained fire officer with a crew shall be arranged to maintain as well as to operate the fire protection systems in case of any need.
32. During construction of the building the following fire protection measures should be provided in good working condition:
    1) Dry riser minimum 100 mm diameter pipe with hydrant outlets on the floors constructed with a fire service inlet to boost the water in the riser from fire service pumps.
    2) Drums filled with water of 2000 liters capacity with two fire buckets on each floor.
    3) A water storage tank of minimum 20000 liters capacity, which may be used for other construction purposes also.

Two staircases are provided. Atleast One staircase should be designated as fire escape staircase and should be pressurized as per the clause 4.4.2.5 of the requirements of National Building Code of India.

As per clause 4.4.2.4.3.2 of the National Building Code of India part IV fire and life safety 2016 – All the staircases shall have minimum width of 1.50 meters without railing. The minimum width of tread without nosing shall be 300 mm for business building and the tread shall be constructed and maintained in a manner to prevent slipping. The maximum height of riser shall be 150 mm for business building and the number shall be limited to 12 per flights.

Every exit, exit access or exit discharge shall be continuously maintained free of all obstructions or impediments to full use in the case of fire or other emergency.

All exits shall provide continuous means of egress to the exterior of a building or to an exterior open space leading to a street.

Exits shall be so arranged that they may be reached without passing through another occupied unit.

As per clause 4.4.2.4.3 (h) (6) of NBC 2016. A staircase shall not be arranged around a lift shaft. Lift shall not open in staircases.

As per clause 4.4.2.4.3.4 of the National Building Code of India part IV fire and life safety 2016- All external stairs shall be directly connected to the ground.

As per clause 4.4.2.1 Table (5) Travel distance of 30m should be provided.

Entrance to the external stairs shall be separate and remote form the internal staircase.

Care shall be taken to ensure that no wall opening or window opens on to or close to an external stairs.

The MSB inspection team has recommended to issue of planning permission / no objection certificate to the proposed building subject to the fulfillment of the above mentioned conditions.

In view of compliance with the above said facts a PP/NOC is issued from the fire service point of view so as to accord planning permission for the above said proposed building subject to fulfillment of all the above said conditions, as recommended by the MSB committee. After completion of this project the compliance certificate should be obtained to ensure fire safety measures.

12.11.24

for Director,
Fire and Rescue Services,
Tamil Nadu.

TAMILNADU FIRE AND RESCUE SERVICES
DIRECTORATE
CHENNAI-8

To:

M/s.Escapade Services LLP,
Plot No.29, Thiru-Vi-Ka Industrial Estate,
Guindy, Chennai – 600 032.

Copy to:

The Joint Director, Fire and Rescue Services,
Northern Region, Chennai.

THE LANDLENS SUITE

Eight ways to know a piece of land before you pay for it.

This report covers one part of the picture. These cover the rest, drawn from the same government records, for any property in Tamil Nadu.

LandLens One
Ask anything about a property and get an answer grounded in live government records, with the sources shown.
/landlens/one

Verify My Land
Every record check run on one property and returned as a single report.
/landlens/verify-my-land

Legal Opinion
An advocate's written opinion on the title, built on the records we pull for it.
/landlens

One Map
Every layer on one map: the parcel, its boundary, zoning, water bodies and what sits around it.
/landlens/one/map

PriceMap
What land actually changed hands for around this plot, taken from the registered deeds.
/landlens/pricemap

Build Scope
What you are allowed to build here: floor space, height, coverage and setbacks.
/landlens/build-scope

Property Tracker
Watch a property and hear about it when something new is registered against it.
/landlens/property-tracker

Deal Room
Run the transaction in one place: documents, stamping, signatures and the parties.
/landlens/deal-room

FREE TOOLS · NO ACCOUNT NEEDED

Twenty-four checks you can run yourself, at no cost.

Records and verification

The registers themselves, read for you.

- Encumbrance Certificate
- Patta and Chitta
- Field Measurement Sketch
- EC Analyzer
- Bank charge check
- Court case search
- Seller background check
- Approval check by survey

Value and duty

What it is worth and what it costs to register.

- Guideline value by street
- Guideline value by survey
- Stamp duty and registration fees
- Capital gains
- Floor space index
- Area unit converter

Zoning and land use

What the plan says can happen on this land.

- Land use zone finder
- CMDA land use check
- Coastal regulation zone
- Master plan check
- Water bodies finder
- Airport height clearance

Registers and directories

Who holds it, and which office keeps the record.

- Find your registering office
- Temple property check
- Waqf property check
- RERA register

Every free tool
/tools

Services we run for you
/services

The LandLens suite
/landlens/one

Verified RealEstate™

Every claim in this document traces back to a government record.

- Legal opinions, due diligence and title verification
- Building plan, layout and sub-division approvals
- Completion and occupancy certificates, regularisation
- Escrow, negotiation and NRI property management
- Land survey, soil testing, architecture and construction

Verified RealEstate
3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai 600 097, India
hello@verified.realestate
+91 9996 12 9996

Prepared from the registers named on the page each finding sits on. Where a register could not be read, this document says so in its place rather than leaving the gap to be read as a clean result.