Verified RealEstate™

Your trusted partner for buying, selling, and managing property, ensuring hassle-free service with 100% transparency.

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai, India

hello@verified.realestate
+91 9996 12 9996
www.verified.realestate

Official Property Record



Digitally Verified Record - Powered by Verified RealEstate™

A.N. MAGESH RAJA, M.E.,
CMDA Registered structural Engineer Grade-I (RSE)
Reg. No: SE / GR - I / 2022 / 06 / 325
Cell : 9787072100
magistructure@gmail.com

STABILITY CERTIFICATE

The detailed engineering and structure design of the proposed building **THE WHITE HOUSE – TOWER B with 18 dwelling units** comprising of Stilt + 3 Floors at Plot no 12,13,14,15,16,17,18,19,20,21,22 & 23, in the layout named MP Villa Vista, S.NO. 26/2A1, Kolapakkam Village, Kundrathur Panchayat Union Limit, Kundrathur Taluk, Kanchipuram District has been done by me based on the report of geotechnical investigation done by **GEO MINES ENGINEERS PVT LTD** Report No **GMEPL/MP DEVELOPERS/315/2024-25** dated 30-09-2024 and considering the functional requirement of the building.

2. It is certified that among other factors, the proposed building has been designed to resist earthquake. I have checked various parameters and found that the proposed building would be safe.

3. I further certify that: (i) The minimum grade of concrete is M25 (ii) The design and analysis has been done using the code of practice for plain and reinforced concrete as per IS 456, design loads as per IS 875 Part I to V and design of earthquake resistant structure for Seismic Zone III as per IS 1893 (Part-I)-2016

4. The building will be safe and sound when used for the purpose for which it is designed.

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

Encl.: Structural Design Calculation

DESIGN OF SLAB

First Floor	Level: + 4.00 m	Dwg No	DWG-THE WHITE HOUSE-ST-GFC-03
Along Grid (BETWEEN A&B-D,23-24)		Slab Reff.	S4 (TWO WAY)

INPUT DATA

Slab

Shorter Span	Lx	=	3.900 m	11.9
Longer Span	Ly	=	6.750 m	3.53
Thickness of Slab	D	=	125 mm	
Clear Cover	d'	=	20 mm	
Ly/Lx ratio	k	=	1.73 Two-Way Slab	

Loads

Dead Load	DL	=	3.13 kN/m^2
Live load	LL	=	2.00 kN/m^2
Floor Finishes	FF	=	1.50 kN/m^2
False Ceilling Load		=	0.25 kN/m^2
Total Load	w	=	6.88 kN/m^2

Panel Type

Basic L/d ratio = 20

Edge Condition: = 7

One Long Edge Continuous

Materials

Grade of Concrete	=	25	N/mm^2
Grade of Reinf. Steel	=	550	N/mm^2
Young's Modulus E		3E+04	N/mm^2

DESIGN

Direction	BM Coefficients (IS:456-2000)	Flexural Design Mu (kNm)	Ast$_{req}$ (mm^2)	Ast$_{pro}$ (mm^2)	dia & Required Spacing 8 (mm)	10 (mm)	12 (mm)	16 (mm)	Provided Reinforcement	
Shorter Span	ax (-) = 0.0905	14.189	319	707	158	246	297	291	10 @ 125	Safe
	ax (+) = 0.0686	10.763	237	707	212	300	297	291	10 @ 125	Safe
Longer Span	ay (-) = 0.0000	0.000	121	452.4	279	270	261	243	8 @ 125	Safe
	ay (+) = 0.0430	6.745	144	452.4	279	270	261	243	8 @ 125	Safe

CHECK FOR DEFLECTION

14

Area of Steel required = 237 mm^2

Area of Steel Provided = 707 mm^2

Steel stress of service load = 107.14 N/mm^2


Provided reinforcement (%) = 0.71%

Modification ratio MF = 2.000

Effective depth required for deflection point of view

d_{req} = 97.5 mm

Eff. depth provided d = 100 mm Safe



SLAB SUMMARY

Shorter Span: Provide T 10 @ 125 mm c/c + 1 T 10 Extra between the two cranked bars

Longer Span : Provide T 8 @ 125 mm c/c + 1 T 8 Extra between the two cranked bars

CHECK FOR SHEAR

Max Shear Force = 20 KN

Actual Shear stress tv = 0.201 N/mm2

P_t of A_{st} = 0.7%

Design Shear Stress tc = 0.56 N/mm^2

Shear is less than Design Shear Stress, Hence Safe against shear

NOTES

1. Crank alternate bars at 0.3 times the respective span.
2. Provide 12mm dia chairs at 1000mm c/c in both directions.
3. Provide 20 mm thick cover blocks at 600mm c/c in both directions.

Reinforcement Summary:

Along Shorter Span

Provided T10@ 125mm c/c

Along Longer Span

Provided T8@ 125mm c/c

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

DESIGN OF FLOOR BEAM (GRID B23 -D23)-FIRST FLOOR

Input Data:	**Beam No**	**:**	B219/(9"X21")		LOAD CASE: 1.5DL+1.5LL		
Breadth			B	=	230	mm	
Overall Depth			D	=	530	mm	380
Clear Cover			d'	=	25	mm	
Effective Depth			d	=	470	mm	
			fy	=	550	N/mm^2	
			fck	=	25	N/mm^2	
Sagging Moments			Mu	=	138.13	kNm	
End moments		LHS	M1	=	177.7	kNm	
		RHS	M2	=	91.04	kNm	
Shear at		END	Vu	=	183.1	kN	
		K	$Mu/(bd^2)$	=	**3.50**	Mpa	

The section is Singly Reinforced Xn

Design Calculation:

Step 1:

For Sagging moments		**Mu**	=	138.13	kNm
		$k = (Mu/bd^2)$	=	2.719	Mpa
		Ast required	=	720	mm^2
		Ast min	=	167	mm^2
Choose dia of bar	**16**	Nos req	=	0.9	Nos
		Dia	=	16	mm
		No	=	5	Nos
		Ast provided	=	1005	mm^2

Provide 5Y16 as Bottom Steel Reinforcement

Step 2:

For End moments	***LHS***	**Mu**	=	177.7	kNm
		$k = (Mu/bd^2)$	=	3.498	Mpa
		Ast required	=	989.6064	mm^2
		Ast min	=	167	mm^2
Choose dia of bar	**16**	Nos req	=	1.2	Nos
		Dia	=	16	mm
		No	=	5	Nos
		Ast provided	=	1005	mm^2

Provide 5Y16 as Top Steel Reinforcement at LHS

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

Step 3:

For End moments	***RHS***	**Mu**	=	91.04	kNm
		k = (Mu/bd^2)	=	1.792	Mpa
		Ast required	=	445.2026	mm^2
		Ast min	=	167	mm^2
Choose dia of bar	16	Nos req	=	0.6	Nos
		Dia	=	16	mm
		No	=	5	Nos
		Ast provided	=	1005	mm^2

Provide 5Y16 as Top Steel Reinforcement at RHS

Step 4:

Top Steel @ Middle

(20% of Max.Mt)		Ast required	=	201	mm^2
Choose dia of bar	16	Nos req	=	0.3	Nos
		Dia	=	16	mm
		No	=	2	Nos

Provide 2Y16 as Top Steel Reinforcement at Middle

Step 5:

Shear Reinforcement

	Vu	=	183.100	kN
	ζv	=	1.694	N/mm^2
	pt	=	0.824	%
	ζc	=	0.600	N/mm^2
	ζc max	=	4.000	N/mm^2
If,			0	
i.ζv <ζc mini shear ,	Here.,			
ii.ζc <ζv >ζcmax design shear.,	**DESIGN SHEAR REQD**			
iii.ζv >ζcmax Increase Depth.				

choose No.of Legs 2 and Choose dia of bar 8

	Asv	=	100.531	mm^2
Design Shear Force	Vus	=	118.24	kN

Spacing of shear reinforement as per

i. Mini Shear Reinf	Sv	=	523	mm	
ii. Design shear-Vertical Stirrups	Sv	=	191.21	mm	whichever is less
iii. Maximum spacing 0.75xd	Sv	=	352.5	mm	
iv. Not greater than 300mm	Sv	=	300	mm	

Provide 2 legged stirrup Y8 @ 100c/c

Step 6:

Results

		Bottom steel			Top steel at Support		Stirrups	
Beam No	**Size**	**Straight**	**Curtail**	**Middle**	**LHS**	**RHS**	**Ends**	**Middle**
B219/(9"X21")	230X530	2Y16	3Y16	2Y16	5Y16	5Y16	2LY8/100	2LY8/200

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

COLUMN / GRID NO. C5 / (B/23)

D E S I G N R E S U L T S

M25 Fe550 (Main) Fe550 (Sec.)

LENGTH: 3400.0 mm CROSS SECTION: 230.0 mm X 380.0 mm COVER: 40.0 mm

LOAD CASE: 120 SHORT (Z)/BRACED LONG(Y)

REQD. STEEL AREA : 2173.95 Sq.mm.

REQD. CONCRETE AREA: 85226.05 Sq.mm.

MAIN REINFORCEMENT: Provide 12 - 16 dia. (2.76%, 2412.74 Sq.mm.)

(Equally distributed)

TIE REINFORCEMENT: Provide 8 mm dia. rectangular ties @ 230 mm c/c

SECTION CAPACITY BASED ON REINFORCEMENT REQUIRED (KNS-MET)

Puz : 1774.02 Muz1 : 106.21 Muy1 : 52.59

INTERACTION RATIO: 0.98 (as per Cl. 39.6, IS456:2000)

SECTION CAPACITY BASED ON REINFORCEMENT PROVIDED (KNS-MET)

WORST LOAD CASE: 120 (1.5DL+1.5EQX+0.45EQZ+TLMIN)

Puz : 1860.89 Muz : 114.93 Muy : 55.85 IR: 0.91

==========

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

Design Code	:	IS 456 + IS 13920 - 2016	
Pilecap No	:	PC1	
Column No	:	C5	(300mm X 380mm)
Grid No	:	B/23	
Concrete Grade	:	M25	
Steel Grade	:	Fe550	
Clear Cover	:	75	mm
Top of pile-cap below ground	:	0.25	m
Density of Soil	=	18	kN/cum
Founding Depth	=	1	m
Pile Capacity in Compression	=	500	kN
Pile Capacity in Tension	=	280	kN
Pile Capacity in Shear	=	20	kN
Pile Capacity Reduction	=	0	%
Pile Overloading	=	10	%
Pile Group Overloading	=	10	%
Pile Capacity Increase for EQ	=	25	%
Pile Capacity Increase for Wind	=	25	%
Live Load Reduction	=	0	%
Consider Capacity Design	:	No	
Consider Overburden Pressure	:	Yes	
No. of Piles	=	2	
Pile Diameter	=	450	mm
Pilecap Offset	=	150	mm
Pile Spacing	=	2.5	x Ø
Pilecap Size	=	1875 X 750	mm
Pilecap Depth	=	750	mm
Soil Wt. + Pile-cap Wt.	=	32.695	kN

For design, moments along shorter direction of pile cap has been ignored

Check for Maximum Load on One Pile:

Critical Analysis Load Combination	:	228	
Critical Load Combination	:	[79] : (LOAD 3: DL) +0.8 (LOAD 4: LL) +0.8 (LOAD 1: EQX) +0.24 (LOAD 2: EQZ) +(LOAD 6: TEM(MAX))	
Pcomb	=	904.96	kN
Ptotal	=	Pcomb + Soil Wt. + Pilecap Wt.	
	=	937.66	kN
Mx	=	4.22	kNm
My	=	-1.05	kNm
P	=	Ptotal/ No. of Piles	
	=	468.83	kN

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

Pmx	=	3.751	kN
Pmy	=	0	kN
Maximum load on pile	=	472.58	kN
Allowable load on pile	=	500 x 1.25	
	=	625	kN

Check for Maximum Load on Pile Group:

Critical Analysis Load Combination	:	203
Critical Load Combination	:	[54] : (LOAD 3: DL) +(LOAD 4: LL) +(LOAD 6: TEM(MAX))
Pcomb	=	886.27 kN
Ptotal	=	Pcomb + Soil Wt. + Pilecap Wt.
	=	918.96 kN
Mx	=	0.53 kNm
My	=	-1.61 kNm
Maximum load on pile group	=	918.96 kN
Allowable load on pile group	=	2 x 500 x 1.1
	=	1100 kN

Check for Maximum shear on Pile Group:

Critical Analysis Load Combination	:	205
Critical Load Combination	:	[56] : (LOAD 3: DL) -(LOAD 1: EQX) +0.3 (LOAD 2: EQZ) +(LOAD 5: TEM(MIN))
Pcomb	=	685.7 kN
Ptotal	=	Pcomb + Soil Wt. + Pilecap Wt.
	=	718.4 kN
Mx	=	-4.68 kNm
My	=	-0.93 kNm
Vx	=	5.53 kNm
Vy	=	-5.56 kNm
Maximum shear on pile group	=	$\text{sqrt}(5.53^2 + -5.56^2)$
	=	7.84 kN
Shear capacity of pile group	=	2 x 20 x 1 x 1.25
	=	50 kN

Check for Uplift Load on Pile:

No uplift in any pile

A.N.MAGESHRAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

Design for Bending:

Bottom Reinforcement Along Column-D

Critical Analysis Load Combination	:	101	
Critical Load Combination	:	[87] : 1.5 (LOAD 3: DL) +1.5 (LOAD 4: LL)	
Pcomb	=	1324.47	kN
Ptotal	=	Pcomb + Soil Wt. + Pilecap Wt.	
	=	1373.513	kN
Mx	=	-1.65	kNm
My	=	-2.34	kNm
Ppile	=	Max Load on pile	
	=	688.22	kN
Deff	=	665	mm
Beff	=	750	mm
DfCol	=	0.37	m
BMux	=	Ppile X DfCol	
	=	256.36	kNm
PtReq	=	0.2	%
AstReq (BM)	=	1330	sqmm/m
AstPrv	=	T16 @ 150 C/C	
	=	1340.4	sqmm/m

Top Reinforcement Along Column-D

D	=	750	mm
	<=	1000	mm, Hence
AstReq (BM)	=	Min Pt for Top Reinforcement X D X 1000	
	=	0.12% X 750 X 1000	
	=	900	sqmm/m
AstPrv	=	T12 @ 125 C/C	
	=	904.8	sqmm/m

Bottom Reinforcement Along Column-B

AstReq (BM)	=	0.2 x (D/2) x 1000/100	
	=	0.2 x 375 x 1000/100	
	=	750	sqmm/m
AstPrv	=	T10 @ 100 C/C	
	=	785.4	sqmm/m

Top Reinforcement Along Column-B

D	=	750	mm
	<=	1000	mm, Hence
AstReq (BM)	=	Min Pt for Top Reinforcement X D X 1000	
	=	0.12% X 750 X 1000	
	=	900	sqmm/m
AstPrv	=	T12 @ 125 C/C	
	=	904.8	sqmm/m

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

Design for One Way Shear:

Along Column-D

Critical Analysis Load Combination	:	102	
Critical Load Combination	:	[88] : 1.5 (LOAD 3: DL) +1.5 (LOAD 4: LL) +(LOAD 6: TEM(MAX))	
Pcomb	=	1327.76	kN
Ptotal	=	Pcomb + Soil Wt. + Pilecap Wt.	
	=	1376.8	kN
Mx	=	-0.02	kNm
My	=	-2.39	kNm
Ppile	=	Max Load on pile	
	=	688.4133	kN

Location of critical section is at d/2 from face of column

Section Location from column center	=	522.5	mm

Data for Piles

Pile No	Load (kN)	% covered	Shear (kN)
P1	688.41	41.11	405.4
P2	688.39	41.11	405.38

Design Shear Force (Vu)	=	Max. of (Shear due to P1, P2)	
	=	405.4	kN
Deff	=	665	mm
Beff	=	750	mm
Tv	=	Vu/(Beff x Deff)	
	=	0.81	N/sqmm
Tc	=	0.33	N/sqmm
Av	=	40	mm
Shear enhancement factor	=	2 X Deff / Av	
	=	33.25	
Enhanced shear strength (Tce)	=	3.1	N/sqmm
Tv	<	Tce, Hence Shear Reinforcement is not required	

Along Column-B

One way shear check do not applicable for 2 pile pile-cap design

Design of Face Reinforcement:

AsfrReq	=	SFR % X D X Beffsfr	
	=	0.05 X 750 X 500 / 100	
	=	188	sqmm
Asfr Prv	=	3-T10	
	=	236	sqmm

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

Check for Load Transfer from Column to PileCap

Critical Analysis Load Combination	=	102	
Critical Load Combination	:	[88] : 1.5 (LOAD 3: DL) +1.5 (LOAD 4: LL) +(LOAD 6: TEM(MAX))	
P	=	1327.76	kN
A2	=	0.11	sqm
A1	=	1.41	sqm
Base Area	=	1.41	sqm
A1	<	Base Area	
Modification Factor	=	SquareRoot(A1/A2) < = 2	
SquareRoot(A1/A2)	=	3.51	
Thus, Modification Factor	=	2	
Concrete Bearing Capacity	=	0.45 X Fck X Modication Factor X Column Area	
	=	2565	kN
Concrete Bearing Capacity	>	P, Hence Safe.	

A.N.MAGESH RAJA, M.E.,(Structural Engineer)
CMDA/GCC REGISTERED STRUCTURAL ENGINEER GRADE-I(RSE)
CMDA REG.No:SE/GR-I/2022/06/325
GCC REG.No:RSE101432021
CELL:97870 72100
magistructure@gmail.com

Our services go beyond

Buying & Selling Services

Property Buying Assistance, Property Selling Support, Market Price Analysis, Owner Outreach and Negotiation.

Legal & Documentation Services

Certified EC, Patta, legal opinions, property verification, due diligence, litigation solutions, and legal heir certificates.

Property Development & Approvals

Building plan approvals, construction, layout and sub-division approvals, zone conversion, and occupancy certification.

NRI & Investment Services

Escrow Services, Rentals, Litigation Solutions, Property Valuation and Property Management

Compliance & Special Services

Demolition, Vaasthu checks, regularization of unauthorized buildings, and office space solutions.

Smarter Tools, Stronger Decisions

Property Valuation & Cost Estimation

Guideline Value, Apartment Composite Value, Stamp Duty & Registration Fees Calculator, Building Value Calculator, Capital Gains Calculator, Area Unit Converter, Length Unit Converter

Ownership, Compliance & Legal Verification

Encumbrance Certificate (EC) Search, Find Your SRO, Temple Property Check, WAQF Property Check, View Patta/Chitta, View FMB, Patta Analyzer, EC Analyzer

Zoning & Land Use Analysis

Land Use Zone Finder, CRZ Zone Check, Aquifer Zone Check, CBA Check, EWS Check, Road Width Check, Proposed Road Widening Check, FSI Calculator

Property Documentation & Workflow Tools

Forms & Templates, Document Generator, Document Translation, Dictionary

Vastu & Property Management Tools

Home Vastu Shastra, Plot Vastu Shastra, Property Management

Verified RealEstate™

Verified RealEstate™

We're honored to be part of your
real estate journey

3/350/2 Mettukuppam,
OMR Thoraipakkam,
Chennai, India

hello@verified.realestate
+91 9996 12 9996
www.verified.realestate